

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-097-21,186-0000

LEASE NAME Parkin "C"

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER 1

2080 Ft. from S Section Line

1980 Ft. from E Section Line

LEASE OPERATOR Vincent Oil Corporation

SEC. 4 TWP. 30 RGE. 18 ~~(N)~~ or (W)

ADDRESS 125 N. Market-Suite 1110, Wichita, Ks. 67202

COUNTY Kiowa

PHONE#(316) 262-3573 OPERATORS LICENSE NO. 5004

Date Well Completed 10/26/85

Character of Well D&A

Plugging Commenced 10/26/85

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 10/26/85

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dodge City, Kansas

Is ACO-1 filed? yes If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. \_\_\_\_\_

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
		0	519	8 5/8	10/16/85	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Plugged well with 135 sxs 60/40 poz, 6% gel as follows: 1149'-50 sxs; 550'-50 sxs; 40'-50 sxs with solid bridge; rathole-15 sxs; mousehole-10 sxs. Plug down at 11:45 p.m. on 10/26/85. Job by B. J. Titan. State Plugger was out of Dodge City, Kansas.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Wheatstate Oilfield Services, Inc. License No. 5149


Address P. O. Box 329, Pratt, Kansas 67124

STATE OF Kansas COUNTY OF Pratt, ss.

Arnie Little (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Arnie Little

(Address) P. O. Box 329, Pratt, Kansas 67124



SUBSCRIBED AND SWORN TO before me this 6th day of November, 1985

Mary L. Tjaden  
Notary Public

My Commission Expires: 3/22/85

RECEIVED  
STATE CORPORATION COMMISSION

NOV 7 1985 Form CP-4 Revised 08-84



**Oilfield Services, Inc.**

- Rotary Drilling
- Drilling Mud and Chemicals
- Heavy Oil Field Hauling
- Roustabout and Dirt Services
- Well Completion and Servicing Units

DRILLER'S WELL LOG

Parkin "C" #1  
 100' N of C NW SE Sec. 4-30S-18W  
 Kiowa County, Kansas  
 Commenced: 10-15-85  
 Completed: 10-26-85  
 API #15-097-21,186  
 Operator: Vincent Oil Corporation

Depth		Formation	Remarks
From	To		
0	546	Sand, Red Bed	Ran 12 joints (506') new, 23# 8 5/8" surface casing. Set at 519' with 200 sxs lite, 3% cc and 100 sxs Class A, 3% cc, 2% gel. Cement did circulate. Plug down at 11:30 a.m. on 10-16-85. Job by B. J. Titan.
546	835	Red Bed, Shale	
835	1600	Red Bed	
1600	2125	Red Bed, Shale	
2125	2182	Shale	
2182	2360	Lime, Shale	
2360	2550	Shale	
2550	5050	Lime, Shale	
5050	5070	Lime	
		T.D.	

RTD 5070'

Plugged well with 135 sxs 60/40 poz, 6% gel as follows: 1149'-50 sxs; 550'-50 sxs; 40'-50 sxs with solid bridge; rathole-15 sxs mousehole-10 sxs. Plug down at 11:45 p.m. on 10-26-85. Job by B. J. Titan. State plugger was out of the Dodge City, Ks. office

STATE OF KANSAS )  
 ) ss  
 COUNTY OF PRATT )

I, the undersigned, being duly sworn on oath, state that the above Driller's Log is true and correct to the best of my knowledge and belief and according to the records of this office.

WHEATSTATE OILFIELD SERVICES, INC.

*Arnie Little*  
 ARNIE LITTLE, PRESIDENT



*Mary L. Tjaden*  
 NOTARY PUBLIC

My Commission expires:

3/22/88

RECEIVED  
 STATE CORPORATION COMMISSION

NOV 7 1985  
 CONSERVATION DIVISION  
 Wichita, Kansas