

STATE OF KANSAS
STATE CORPORATION COMMISSION
Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH

Locate well correctly on above
Section Plat

Barton County. Sec. 13 Typ. 20S Rge. 11W (E) (W)
Location as "NE/CNW&SW¼" or footage from lines NE/4
Lease Owner Great Bend Pipe & Supply Company
Lease Name Peters Well No. 6
Office Address Box 414 - Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) OIL
Date well completed 9-16-48 19
Application for plugging filed May 17, 1956 19
Application for plugging approved May 18, 1956 19
Plugging commenced May 21 19 56
Plugging completed May 24 19 56
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Brundge
Producing formation Arbuckle Depth to top 3270 Bottom 3274 Total Depth of Well 3274 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	159'	None
				5-1/2"	3272'	2645'
				Casing perforated at 3271'.		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled the hole with sand from 3274' to 3260' and ran 5 sacks of cement. Pulled part of casing out and circulated the hole with 18 sacks of jell mud. Set a 10' rock bridge from 200' to 190' and ran 20 sacks of cement which filled to 118'. Mudded the hole to 35', set a 10' rock bridge and ran 10 sacks of cement to fill to base of cellar. Plugging completed.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor West Supply Co., Inc.
Address Chase, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
Nathan Meltzer (employee of-owner)-or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Nathan Meltzer
Nathan Meltzer, Box 414, Gt. Bend, Ks. (Address)

SUBSCRIBED AND SWORN TO before me this 29th day of May, 19 56

My commission expires 3-30-57

Anne Meltzer Notary Public.
RECEIVED
STATE CORPORATION COMMISSION
MAY 30 1956
5-30-56
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC. 13 T. 20 R. 11W
BOOK PAGE 62 LINE 28

Peters No. 6 Well

Sec. 13-20-11W, Barton County, Kansas

Drilled for: National Cooperative
Ranch Association

Drilled by: Mouser Drilling Company

Drilling Commenced: September 1948
Drilling Completed: September 1948Casing Record:8 5/8" 159'
5 1/2" 3272' 1 1/4" O.D. 8 rd thd Casing

FORMATION	DEPTH
Cellar	4
Surface clay	18
Sand	65
Sharp sand	90
Blue shale	159
Shale	160
Red bed	460
Anhydrite	475
Shale and shells	950
Salt	1230
Shale and shells	1280
Shale and lime	1375
Lime and shale	1590
Shale and lime	1635
Flint	1665
Lime	1740
Lime and shale	1860
Shale and shells	1955
Lime and shale	2055

FORMATION	DEPTH
Shale and shells	2320
Lime and shale	2610
Lime	2914
Shale	2972
Lime and shale	3005
Lime	3271
Arbuckle	3272
Total Depth	3272'

STATE OF KANSAS

SS:

COUNTY OF SEDGWICK

I, the undersigned, being duly sworn on oath, state that the above and within statement is a true and correct record and log of the well drilled on the above described location to the best of my knowledge and belief.

B. H. MouserSubscribed and sworn to before me this 29th day of September 1948.

My Commission Expires:

March 18, 1950Francis L. Webber

PLUGGING
FILE SEC. 13-20-11W
BOOK PAGE 49 LINE 3

STATE OF KANSAS
CONSERVATION DIVISION
WICHITA, KANSAS