

STATE OF KANSAS  
STATE CORPORATION COMMISSION


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Barton County. Sec. 13 Twp. 20 Rge. 11 E/W  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines

SE NE NW

Lease Owner National Cooperative Refinery Assn.  
Lease Name Peters #11 Well No. \_\_\_\_\_  
Office Address Great Bend, Kansas 67530  
Character of Well (Completed as Oil, Gas or Dry Hole) \_\_\_\_\_



Locate well correctly on above Section Plat

Date Well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging approved \_\_\_\_\_ 19\_\_\_\_  
Plugging commenced 9/25/76 \_\_\_\_\_ 19\_\_\_\_  
Plugging completed 9/29/76 \_\_\_\_\_ 19\_\_\_\_  
Reason for abandonment of well or producing formation \_\_\_\_\_  
depleted.  
If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Rankin  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3274  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	151	none
				5 1/2"	3267	1816'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Sanded to 3000' and ran 5 sacks cement. Shot pipe at 1805' and pulled 60 joints. Squeezed hole with 3 sacks hulls, 15 sacks gel, released plug and displaced with 100 sacks common cement with 8% gel added.

PLUGGING COMPLETE,

RECEIVED  
STATE CORPORATION COMMISSION

OCT 01 1976 10-1-76

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor KELSO CASING PULLING  
CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.  
R. DARRELL KELSO (employee of owner) or (owner or operator)  
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso  
CHASE, KANSAS  
(Address)

SUBSCRIBED AND SWORN TO before me this 30th day of Sept., 19 76

My commission expires



Margaret Melcher  
Notary Public.

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas


**COPY**

Company. NAT'L COOP. REFG. ASSOC.  
Farm. Petors No. 11

SEC. 13 T. 20 R. 11W  
SE NE NW

Total Depth. 3270  
Comm. 7-20-51 Comp. 7-29-51  
Shot or Treated.  
Contractor. J. W. Braden Drlg. Co.  
Issued. 9-29-51

County Barton  
KANSAS



Elevation. 1756

Production. 44 bbls.

Figures Indicate Bottom of Formations.

sand, shale & shells	151
shale & red bed	820
shale	1200
shale & anhydrite	1320
shale & shells	1735
lime	2130
lime & broken shale	2340
lime	2400
shale & lime	2620
lime	2915
shale & lime	3010
lime	3267½
lime	3270
Total Depth	

Scout Tops:	
Heebner	2861
Lansing	3020
Arbuckle	3266

RECEIVED  
STATE CORPORATION COMMISSION

SEP 13 1976

CONSERVATION DIVISION  
Wichita, Kansas