

STATE OF KANSAS
STATE CORPORATION COMMISSION
Give All Information Completely
Make Required Affidavits
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Barton County, Sec. 13 Twp. 20 Rge. 11 (E) W (W)

Location as "NE/CNW%SW%" or footage from lines SW SW SE
Lease Owner M. F. Barnes
Lease Name Mary Meyer Well No. 1
Office Address P. O. Box 877, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 3-18-64 19
Plugging completed 3-24-64 19
Reason for abandonment of well or producing formation Depleted.

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Don Truan
Producing formation Depth to top Bottom Total Depth of Well 3262 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10-3/4"	127'	None
				7"	3262'	1504'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked hole to 3262', sanded hole to 3260' and dumped 5 sacks of cement @ 3260' with dump bailer. Pulled 7" casing to 300' and pumped in 15 sacks of gel mud. Pulled 7" casing to 200' and pumped in 30 sacks of cement. Pulled balance of 7" casing, bailed hole to 40', set rock bridge to 30' and ran 15 sacks of cement to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION

PLUGGING COMPLETE.

MAR 31 1964

CONSERVATION DIVISION
Wichita, Kansas

3-31-64

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KNIGHT CASING PULLING COMPANY
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.
Noel J. Knight (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Paul J. Knight
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 27th day of March, 1964

My commission expires May 20, 1964

Notary Public.

Well Log for Mary Meyer #1, located C SW SW SE Sec. 13-20S-11W, Barton County, Kansas

0 to 78' Sand
 97 Shale
 128 Shale & shells
 450 Red bed & shale
 885 Shale & shells
 1210 Shale & salt
 1240 Shale & shells
 1340 Shale & lime
 1420 Lime
 1470 Lime & shale
 1655 Shale & shells
 1790 Lime
 1813 Shale & shells
 1930 Lime & shale
 2010 Lime
 2130 Shale & shells
 2280 Lime & shale
 2359 Shale & lime shells
 2473 Lime & shale
 2560 Shale & lime shells
 2590 Shale & lime
 2619 Lime
 2630 Lime & shale
 2640 Lime
 2661 Shale & lime
 2797 Lime
 2864 Lime & shale
 2925 Lime
 2995 Shale & shells
 3011 Shale
 3018 Lime & shale
 3031 Lime
 3139 Lime & shale
 3195 Shale & shells
 3221 Lime & shale
 3262 Lime
 TOTAL DEPTH - - - 3335 Silicious lime
 P. B. to 3330

GULF OIL CORPORATION
 316 UNION CENTER BUILDING
 WICHITA, KANSAS

3-18-64