

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

Barton County, Sec. 13 Twp. 20 Rge. 11 (E) (W)

Location as "NE/CNW/SW" or footage from lines NE SE NE

Lease Owner National Cooperative Refinery Association

Lease Name Peters Well No. 7

Office Address \_\_\_\_\_

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed October 8, 19 48

Application for plugging filed October 9, 19 53

Application for plugging approved October 10, 19 53


Plugging commenced November 13, 19 53

Plugging completed November 15, 19 53

Reason for abandonment of well or producing formation Depletion of  
Producing formation.

If a producing well is abandoned, date of last production September 30, 19 53

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above  
Section Plat

Name of Conservation Agent who supervised plugging of this well G. D. Stough

Producing formation Arbuckle Depth to top 3282 Bottom \_\_\_\_\_ Total Depth of Well 3300 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	160'	Cemented
				5 1/2"	3284'	2647'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with sand from 3300' to 3250' and ran 5 sacks of cement. Pumped in 60 barrels Gel Mud and 15 sacks cement. Mudded hole to top and ran 10 sacks cement on up to base of cellar.

11-21-53

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor West Supply Company  
Address Chase, Kansas.

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
C. R. Sears (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. R. Sears


(Address)

SUBSCRIBED AND SWORN TO before me this 20 day of November, 19 53

C. Orville May  
Notary Public.

My commission expires June 30, 1954.

C. Orville May



Peters No. 7 Well

Drilled for: National Cooperative Refinery Association

Sec. 13-20-11W, Barton County, Kansas

Drilled by: Mouser Drilling Company

Drilling Commenced: September 20, 1948

Drilling Completed: October 1, 1948

Casing Record

8 5/8" 160'  
5 1/2" 3286' 1 1/4" O.D. 8 rd thd Casing

<u>FORMATION</u>	<u>DEPTH</u>	<u>FORMATION</u>	<u>DEPTH</u>
Cellar	4		
Shale	20		
Sand	70		
Sharp sand	90		
Blue shale	160		
Red bed	457		
Anhydrite	470		
Shale and shells	930		
Salt	1200		
Shale	1315		
Lime and shale	1500		
Shale and lime	1632		
Flint	1660		
Lime and shale	2095		
Shale and shells	2130		
Lime and shale	2615		
Lime	2930		
Shale	2959		
Lime and shale	2992		
Lime	3285		
Conglomerate	3288		
Arbuckle lime	3290		
Total Depth	3290'		

RECORDED  
INDEXED  
OCT 10 1948  
STATE OF KANSAS  
DEPARTMENT OF REVENUE

STATE OF KANSAS

SS:

COUNTY OF SEDGWICK

I, the undersigned, being duly sworn on oath, state that the above and within statement is a true and correct record and log of the well drilled on the above described location to the best of my knowledge and belief.

B. Mouser

Subscribed and sworn to before me this 29th day of October 1948.

My Commission Expires:

March 18, 1950

Frances L. Webber

PLUGGING  
FILE SEC 13 T20 R 114  
BOOK PAGE 134 LINE 45