

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 10 S. Market, Room 2078
 Wichita, KS 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15.009.07237.0000

LEASE NAME Peters

WELL NUMBER #8

4950 Ft. from S Section Line

990 Ft. from E Section Line

SEC. 13 TWP. 20 RGE. 11 (E) or (W)

COUNTY Barton

Date Well Completed 1950

Plugging Commenced 6-26-98

Plugging Completed 6-29-98

RECEIVED
 STATE CORPORATION COMMISSION

7-10-98
 JUL 10 1998

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

CONSERVATION DIVISION
 Wichita, Kansas

EASE OPERATOR Richlan Drilling

ADDRESS 598 2nd. Ave. Beaver, Kansas 67517

PHONE# (316)587-3605 OPERATORS LICENSE NO. 31086

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on _____ (date)

by Case Morris (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3272'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	161'	None
				5-1/2"	3270'	1390'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each section. Bridge @1400', damped 3 sacks cement on top. Shot casing @1390', pulled to 1300', pumped 90 sks. cement and 300# hulls, pulled to 500', pumped 40 sks. cement and 100# hulls, pulled to 150' and circulated cement to top. Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Richlan Drilling

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed therewith, and the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 8th day of July, 1998

[Signature]
 Notary Public

My Commission Expires: _____

