

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15.009.22826.0000

API NUMBER 15-009-22,826

LEASE NAME Scheuffler

WELL NUMBER #3

SPOT LOCATION NE NW NW

SEC.16 TWP.20 RGE.11 (E) or (W)

COUNTY Barton

Date Well Completed

Plugging Commenced 10-30-87

Plugging Completed 11-5-87

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Isern-Schultz Oil & Gas, Inc.

ADDRESS Box 486, Ellinwood, Ks. 67526

PHONE #316-564-2240 OPERATORS LICENSE NO. 5083

Character of Well oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Six (6)

Is ACO-1 filed? If not, is well log attached? With application

Producing formation Depth to top bottom T.D. 3290'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	265'	None
				5-1/2"	3286.5	2,446.94'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Dumped sand to 3230' and 5 sacks cement. Shot casing at 2730', 2600' and 2400'. Pulled 63 joints of 5-1/2" casing. B.J. Titan squeezed well with 3 sacks hulls and 80 sacks Thrifty-mix cement blended with one sack hulls. Maximum pressure was 900 psi and shutin 900 psi.

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111

Address Box 698, Great Bend, Kansas 67530

STATE OF Kansas COUNTY OF Barton, ss.

James W. Rockhold (employee of operator) or
(operator) of above-described well, being first duly sworn on oath, says: That
I have knowledge of the facts, statements, and matters herein contained and
the log of the above-described well as filed that the same are true and
correct, so help me God.

STATE CORPORATION COMMISSION

(Signature) James W. Rockhold
James W. Rockhold
(Address) Box 698, Gt. Bend, Ks. 6753

NOV 9 1987

11-9-87

SUBSCRIBED AND SWORN TO before me this 6th day of November, 1987



IONA M. LEATHERMAN
Barton County, Kansas
My Appt. Exp. 2-26-91

My Commission expires:

Iona M. Leatherman
Notary Public