

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-097-01,002-000

LEASE NAME Fincham #1

WELL NUMBER _____

SPOT LOCATION 660' FNL, 660' FEL

SEC. 3 TWP. 30S RGE. 18W (E) or (W)

COUNTY Kiowa

Date Well Completed _____

Plugging Commenced 11/14/84

Plugging Completed 11/28/84

LEASE OPERATOR TXO Production Corp.
ADDRESS 200 W. Douglas, Suite 300, Wichita, Ks. 67202

PHONE # (316) 265-9441 OPERATORS LICENSE NO. 5171

Character of Well _____
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom T.D. 4983'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	530'	none
				4 1/2"	4982'	3796'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Pumped bottom with 35 sacks cement 3% c.c. stopped plug at 4509'. Shot pipe at 4212' & 3796'. Pulled 93 joints of pipe. Pumped well with 2 hulls, 10 gel, 50 cement, 10 gel, 1 hull, & 125 sacks 60/40 poz 2% gel 3% c.c.

Plugging complete

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050
Address Box 347, Chase, Ks. 67524

RECEIVED
STATE CORPORATION COMMISSION

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso

(employee of operator) or


(operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) Box 347, Chase, Ks. 67524

DEC 07 1984
12-7-84
CONSERVATION DIVISION
Wichita, Kansas

SUBSCRIBED AND SWORN TO before me this 6th day of December, 1984



My Commission expires: _____

Irene Hoover
Notary Public