

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-009.20046.0000

LEASE NAME Morris

WELL NUMBER A-2

SPOT LOCATION 150' W of SE NE SW

SEC. 31 TWP 20S RGE. 13W(E) or (W)

COUNTY Barton

Date Well Completed _____

Plugging Commenced 6-5-86

Plugging Completed 6-13-86

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Brougher Oil, Inc.

ADDRESS Drawer 1367 Great Bend, Kansas 67530

PHONE (316) 793-5610 OPERATORS LICENSE NO. 6393

Character of Well Oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays, Kansas

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom _____ T.D. 3538'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	249'	none
				5-1/2"	3535'	2183'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from _____ feet to _____ feet each set.

Plugged off bottom with sand to 3250' and 5 sacks cement. Shot pipe @2806', 2605', 2412', 2183', pulled a total of 70 joints of 5-1/2" casing. Plugged surface with 7 sacks hulls and 100 sacks econolite.
Plugging Complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling, Inc. License No. 6050
Address P.O. Box 347 Chase, Kansas 67524


STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso, President (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says that I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) Box 347 Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 19th day of June, 1986



My Commission expires: _____

Notary Public

15.009.20046.0000

MORRIS "A" #2 (Formerly Benjamin "A" #2)
150' W of SE NE SW
Sec 31-20s-13w
Barton County, Kansas

RECEIVED
STATE CORPORATION COMMISSION
MAY 30 1980
CONSERVATION DIVISION
Wichita, Kansas

Originally Drilled: 4/30/67 by Dean & Clark, Inc. as their #2 BENJAMIN "A"
Originally Completed: 10/12/67
Bought by Brougner Oil, Inc. 1/1/72
RTD: 3538'
Surface Casing: 8" set at 249' with 250 sacks cement
Production Casing: 5" set at 3535'
OPEN HOLE COMPLETION in the ARBUCKLE from 3535-3538'
PERFORATED: LKC "A" 3299-3303, LKC "B" 3328-3331, LKC "D" 3341-3344, LKC "J"
3453-3457, CONGLOMERATE 3507-3509 and 3514-3516'.

P.B. ~~3502~~
3502