

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Kiowa SEC. 25 TWP. 30S RGE. 18W E/W
Location as in quarters or footage from lines:
SW SW

Locate Well
correctly on above
Section Platt.

Lease Owner Maurice L. Brown Co.
 Lease Name HANTLA "B" Well No. 1
 Office Address 200 Sutton Place, Wichita, KS 67202
 Character of Well (Completed as Oil, Gas or Dry Hole) Dry Hole
 Date Well Completed June 22, 1981
 Application for plugging filed June 22, 1981
 Plugging commenced June 22, 1981
 Plugging completed June 22, 1981
 Reason for abandonment of well or producing formation
No commercial quantity of oil or gas encountered.
 Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well Leo Massey
 Producing formation _____ Depth to top _____ bottom T.D. 5225'
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set 1st plug @ 720' with 40 sx.
Set 2nd plug @ 500' with 50 sx.
Set 3rd plug @ 40' with 10 sx.
Job was complete @ 6:30 p.m., 6/22/81.

(If additional description is necessary, use BACK of this sheet)
 Name of Plugging Contractor Abercrombie Drilling, Inc.
 RECEIVED
 STATE CORPORATION COMMISSION
7-10-81
JUL 10 1981


STATE OF Kansas COUNTY OF Sedgwick, ss.
 Jack L. Partridge, Vice President (employee of owner) or (owner or operator) of the
 above-described well, being first duly sworn on oath, says: That I have knowledge of the
 facts, statements, and matters herein contained and the log of the above-described well as
 filed and that the same are true and correct. So help me God.

(Signature) Jack L. Partridge
801 Union Center, Wichita, KS 67202
 (Address)

SUBSCRIBED AND SWORN TO before me this 7th day of July, 19 81

Suzanne M. Hofer
 Suzanne M. Hofer, Notary Public.

My commission expires: 2-4-85



CONTRACTOR'S WELL LOG

OPERATOR: Maurice L. Brown Co.
 CONTRACTOR: Abercrombie Drilling, Inc.
 WELL NAME: HANTLA "B" #1
 LOCATION: SW SW, Section 25-30S-18W
 Kiowa County, Kansas
 SPUD DATE: 6/06/81
 COMPLETION DATE: 6/22/81

0	455	Red Bed & Shale
455	980	Lime & Shale & Red Beds
980	1000	Red Bed & Shale
1000	1405	Lime & Shale
1405	1410	Red Bed & Shale
1410	5132	Lime & Shale
5132	5137	Lime
5137	5225	Lime & Shale

Spud hole @ 9:30 p.m., 6/06/81. Ran 11 joints of 8 5/8" 24# casing set @ 507.61'. Cemented with 250 sx. of Halco Lite, 3% c.c., 1/2# Flocel per sack. Plug was down @ 3:25 a.m., 6/07/81. Cement did circulate.

TD @ 5225'. Set 1st plug @ 720' with 40 sx. Set 2nd plug @ 500' with 50 sx. Set 3rd plug @ 40' Solid Bridge with 10 sx. 5 sx. in Rathole, 50-50 posmix, 6% Gel. Job complete @ 6:30 p.m., 6/22/81.

STATE OF KANSAS)
)
 COUNTY OF SEDGWICK)

Jack L. Partridge, Vice President of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the HANTLA "B" #1, SW SW, Section 25-30S-18W, Kiowa County, Kansas.

ABERCROMBIE DRILLING, INC.

BY: Jack L. Partridge
 Jack L. Partridge, Vice Pres.

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 7th day of July, 1981.

Suzanne M. Hofer
 Suzanne Hofer, Notary Public

2-4-85

RECEIVED
 STATE CORPORATION COMMISSION

JUL 10 1981
 CONSERVATION DIVISION
 Wichita, Kansas

