

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

OR

Strike out upper line
when reporting plug-
ging off formations.

FORMATION PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

NORTH

A 4x4 grid with a single black dot in the top-right cell.

**Locate well correctly on above
Section Plat**

.....BARTON.....County. Sec. 31 Twp 20S Rge. (E) 13 (W)
Location as "NE¼NW¼SW¼" or footage from lines. SW NW NE
Lease Owner. Producers Pipe & Supply Co.
Lease Name. W.L. Hiss Well No. 2
Office Address. Box 1814, Tulsa, Okla.
Character of Well (completed as Oil, Gas or Dry Hole). Oil
Date well completed. 1936
Application for plugging filed. May 18, 1948
Application for plugging approved. May 19, 1948
Plugging commenced. June 3, 1948
Plugging completed. June 9, 1948
Reason for abandonment of well or producing formation. Exhausted
If a producing well is abandoned, date of last production. May or June 1947.
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Section Flat

Name of Conservation Agent who supervised plugging of this well Charlie Stough, Great Bend, Kansas

Producing formation K. City-Lansing Depth to top 3205 Bottom 3390 Total Depth of Well 3390 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Surface	H ₂ O			13"	16413"	None
K.C.-Lansing	Oil	3205'	3390'	7"	3232'	2720'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Fill with mud from 3228' to 3180'.
Run 6 sacks cement from 3180' to 3150'.
Fill with mud from 3150' to 168'.
Halliburton Co. Run 40 Sacks cement to 140'.
Fill with mud from 140' to 20'.
Cap with 10 sacks cement from 20' to cellar.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to.....Producers Pipe & Supply Co.,
Address.....Box 1814, Tulsa, Okla.

STATE OF OKLAHOMA, COUNTY OF TULSA, SS.
JACK SATIN (employee of owner) ~~or (owner or operator)~~ of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. PRODUCERS PIPE & SUPPLY CO.,

(Signature) By Jack Satin
Jack Satin
Box 1814, Tulsa, Okla.
 (Address)

SUBSCRIBED AND SWORN to before me this 30th day of June 19 48

My commission expires,

22-2625

2-48--15M

Notary Public.

