

WELL PLUGGING RECORD

All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Blitting Building  
Wichita, Kansas

Barton

County. Sec. 31 Twp. 20 Rge. 13 (B) (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SW NE SE

Lease Owner Petroleum, Inc.

Lease Name Benjamin 'B' Well No. 2

Office Address 100 Derby Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed January 17, 19 51

Application for plugging filed January 17, 19 51

Application for plugging approved January 22, 19 51

Plugging commenced January 17, 19 51

Plugging completed January 17, 19 51

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. C. D. Stough

Producing formation Depth to top Bottom Total Depth of Well 3605 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	225'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Wooden plug set at 220'. Cemented and displaced through drill pipe 15 sax. Filled hole with heavy mud to 30'. Placed wooden plug at 30'. Filled hole to surface with 10 sax cement.

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 25 1951  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Petroleum, Inc.  
Address 100 Derby Bldg., Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, SS.

Eric H. Jager

(employee of owner) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Eric H. Jager

100 Derby Building, Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 23rd day of January, 19 51

Charlotte Heidman

Notary Public.

My commission expires October 13, 1954

28-8273-s 4-50-10M

PLUGGING  
FILE SEC 31 20R 132  
BOOK PAGE 56 LINE 38

15.009.05672.0000

WELL LOG BENJAMIN 'B' #2

Petroleum, Inc., Lease Owner

Section 31, Twp. 20S, Rge. 13W

Garvey Oil, Contractor

Location: SW NE SE

Rotary Total Depth: 3605'

County: Barton, Kansas

Commenced: January 3, 1951

Production: D & A

Completed: January 17, 1951

Elevation: 1907 D.F.

Casing: 225' of 8 5/8"

Figures below indicate bottom of formation:

30	Surface Soil & Clay		<u>Tops:</u>
105	Sand & Clay		
165	Sand & Shale	3178	Heebner
225	Shale & Shells	3196	Toronto
310	Sand	3215	Base Oread
340	Sand & Clay	3291	Brown Lime
370	Red Bed	3302	Lansing
815	Anhydrite	3536	Conglomerate
1299	Shale & Shells		
1870	Lime & Shale		
2465	Shale		
2835	Lime & Shale		
2960	Shale		
3032	Shale & Shells		
3110	Lime		
3292	Shale		
3364	Lime		
3605	R.T.D.		

**RECEIVED**  
STATE CORPORATION COMMISSION  
JAN 25 1951  
CONSERVATION DIVISION  
Wichita, Kansas

D & A

I hereby certify that this is a true and correct log of the above mentioned well.

PETROLEUM, INC.

*Eric H. Jager*  
Eric H. Jager

**PLUGGING**  
FILE SEC 31 T 20 R 13W  
BOOK PAGE 56 LINE 39

STATE OF KANSAS: SS.  
SEDGWICK COUNTY:

Subscribed to and sworn to before me, a Notary Public in said County and State this 23rd day of January, 1951.

My commission expires: 10-13-54

*Charlotte Waldman*  
Notary Public