

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

NORTH

Locate well correctly on above
Section Flat

Barton County. Sec. 31 Twp. 20 Rge. 13 (E) (W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NE SE SE
Lease Owner Petroleum, Inc.
Lease Name Benjamin 'B' Well No. 3
Office Address 100 Derby Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed March 12, 1951
Application for plugging filed March 12, 1951
Application for plugging approved March 12, 1951
Plugging commenced March 12, 1951
Plugging completed March 12, 1951
Reason for abandonment of well or producing formation Dry Hole
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well
Producing formation Depth to top Bottom Total Depth of Well 3570' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	219'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Wooden plug set at 218'. Cemented and
displaced through drill pipe 15 sax.
Filled hole with heavy mud to 30'. Placed
wooden plug at 30'. Filled hole to bottom
of cellar with 10 sax cement.

MAR 14 1951

3-14-51

WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Petroleum, Inc.
Address 100 Derby Building, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
W. W. Fisher (employee of owner) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W W Fisher

100 Derby Building, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 13th day of March, 1951

Charlotte Heidman

Notary Public.

My commission expires October 13, 1954

28-3273-s 4-50-10M

PLUGGING

FILE SEC-31-T-20-R (34)

WICHITA, KANSAS

WELL LOG BENJAMIN 'B' #3

Petroleum, Inc., Lease Owner

Section 31, Twp. 20S, Rge. 13W

Garvey Oil, Contractor

Location: NE SE SE

Rotary Total Depth: 3570'

County: Barton

Commenced: March 2, 1951

Production: D & A

Completed: March 10, 1951

Elevation: 1910 D.F.

Casing: 219' of 8 5/8"

Figures below indicate bottom of formation:

		<u>Tops:</u>
219	Sand & Shale	
797	Shale, Sand & Shells	
820	Anhydrite	
1035	Red Bed & Shale	3185 Heebner
1318	Shale & Shells	3205 Toronto
1585	Salt & Shale	3300 Brown Line
1650	Shale & Shells	3310 Lansing
1960	Lime & Shale	3527 B.K.C.
2105	Lime	3543 Conglomerate
2220	Lime & Shale	3565 Arbuckle
2685	Shale & Shells	
2900	Lime & Shale	
3250	Lime	
3318	Shale & Lime	
3555	Lime	
3565	Cong. & Shale	
3570	Arb. Lime	
3570	R.T.D.	

I hereby certify that this is a true and correct log of the above mentioned well.

PETROLEUM, INC.

W. W. Fisher
W. W. Fisher

STATE OF KANSAS:

: SS.

SEDGWICK COUNTY:

Subscribed to and sworn to before me, a Notary Public in said County and State this 13th day of March, 1951.

RECEIVED
STATE CORPORATION COMMISSION

Charlotte A. Anderson
Notary Public

My commission expires: 10-13-51
MAR 14 1951

PLUGGING

1078 SEC 31 T 20 R 13W

PAGE 67 LINE 6

CONSERVATION DIVISION
Wichita, Kansas