


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Barton County. Sec. 31 Twp. 20S Rge. 13W(E) (W)

Location as "NE/CNW/SW" or footage from lines SW SW NW

Lease Owner Alpine Oil & Royalty Co., Inc.

Lease Name Murray Well No. 1

Office Address 800 Bitting Building, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) dry hole

Date well completed February 18, 1967 19

Application for plugging filed February 18, 1967 (by phone) 19

Application for plugging approved February 18, 1967 (by phone) 19

Plugging commenced February 18, 1967 19

Plugging completed February 18, 1967 19

Reason for abandonment of well or producing formation nonproductive in commercial quantities

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Donald Truan

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3 680 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	292 ft.	Cemented

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Weld collar on surface mud in hole; squeezed with 90 sacks cement one plug.

RECEIVED
STATE CORPORATION COMMISSION
MAR 1 1967
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Gabbert-Jones, Inc.

Address Sutton Place, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.

Dwight J. Wilson (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) Dwight J. Wilson

(Address) _____

SUBSCRIBED AND SWORN TO before me this 28 day of February, 1967

Evelyn Wan ko
Evelyn Wan ko
Notary Public.

My commission expires December 10, 1968



15-009-20018-00-00

GABBERT-JONES, INC.
WICHITA, KANSAS
DRILLERS' WELL LOG

Murray #1
SW SW NW Section 31-20S-13W
Barton County, Kansas

COMMENCED: February 10, 1967
COMPLETED: February 19, 1967

OPERATOR - Alpine Oil & Royalty Co., Inc.

DEPTH		FORMATION	REMARKS
From	To		
0	185	Sand	
185	287	Shale and sand	Ran 13 joints of 8-5/8" casing, set @ 287' w/280 sacks cement.
287	665	Sand and shale	
665	785	Shale and red bed	
785	815	Anhydrite	
815	1350	Shale and shells	
1350	1600	Shale	
1600	1780	Lime and shale	
1780	1965	Lime	
1965	2975	Lime and shale	
2975	3125	Lime	
3125	3284	Lime and shale	
3284	3540	Lime	
3540	3650	Lime and shale	
3650	3680	Arbuckle	
3680	TD		Dry and abandoned

RECEIVED
STATE CORPORATION COMMISSION
MAR 7 1967
CONSERVATION DIVISION
Wichita, Kansas

I, E. E. HALL, certify this is a correct copy of the Drillers' Log for the well drilled in the SW SW NW Section 31-20S-13W, Barton County, Kansas, to the best of my knowledge and belief.

E. E. Hall
E. E. HALL

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

Before me, the undersigned, a Notary Public within and for said County and State, on this 23rd day of February, 1967, personally appeared E. E. HALL, to me personally known to be the identical person who executed the within and foregoing instrument and acknowledged to me that he executed the same as his free and voluntary act and deed, for the uses and purposes therein set forth.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal the day and year last above written.

Barbara J. Layton
Barbara J. Layton, Notary Public

My Commission Expires February 1, 1968.