

15.135.20866.0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217

Locate well correctly on above
Section Plat

Ness County, Sec. 15 Twp. 20 Rge. 23 (E) W (W)
Location as "NE/CNWSW" or footage from lines SW NE
Lease Owner Phillips Petroleum Company
Lease Name Sutton 'AB' No. 1 Well No. 1
Office Address Box 287, Great Bend, Kansas 67530
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 4/14/74 19
Application for plugging filed 4/14/74 19
Application for plugging approved 4/14/74 19
Plugging commenced 4/14/74 19
Plugging completed 4/14/74 9:25 p.m. 19
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey
Producing formation Depth to top Bottom Total Depth of Well 4480 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	8-5/8"			8-5/8"	499'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

75 sacks @ 4460 4460-4260'
50 sacks @ 1160 1160-1060'
50 sacks @ 560 560-460'
15 sacks @ 40' 40' to surface
Job complete 9:25 p.m. 4/14/74

RECEIVED
STATE CORPORATION COMMISSION
MAY 2 - 1974
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Slawson Drilling Company
Address 408 One Twenty Bldg, Wichita, Kansas 67202

STATE OF Kansas COUNTY OF Barton ss.
C. D. Dohrer (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. D. Dohrer Prod. Supt.

Box 287, Great Bend, Kansas 67530
(Address)

Subscribed and Sworn to before me this 1st day of May, 1974

My commission expires 10-27-77

Notary Public.

DRILLERS LOGElevation: 2281 K.B.

COMPANY: Phillips Petroleum Company
Box 287
Great Bend, Kansas 67530

LEASE NAME: SUTTON 'AB' No. 1
SW NE
Sec. 15-20-23W
Ness County, Kansas

CONTRACTOR: Slawson Drilling Company, Inc.
408 One Twenty Building
Wichita, Kansas 67202

TOTAL DEPTH: 4480'

COMMENCED: 4/5/74

COMPLETED: 4/14/74

CASING: 499' 8-5/8" set @ 502' with 300 sacks cement

0 to 140'	Post Rock & clay
140 to 502'	Shale
502 to 873	Shale & shells
873 to 885	Blaine Lime
885-to 920	Shale
920 to 1488	Shale & Shells
1488 to 1544	Anhydrite
1544-to 1708	Shale & shells
1708 to 2390	Shale & Lime
2390 to 3752	Lime & shale
3752 to 3904	Lime
3904 to 4035	Lime & shale
4035 to 4391	Lime
4391 to 4420	Lime & Sand
4420 to 4480	Sand & Shale, Miss
4480	RTD

RECEIVED
STATE CORPORATION COMMISSION
MAY 2 - 1974
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS
COUNTY OF SEDGWICK

I, James C. Remsberg, of the Slawson Drilling Company, Inc.,
upon oath state that the above and foregoing is a true and correct copy of the
log of the Sutton 'AB' No. 1 well.

James C. Remsberg
James C. Remsberg

Subscribed and sworn to me on April 30, 1974

Mary Lou Taylor
Mary Lou Taylor, Notary

My commission expires January 17, 1977

