15.135.20380.0000


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

NORTH



Locate well correctly on above Section Plat

Ness County. Sec. 15 Twp. 20S Rge. (E) 23 (W)

Location as "NE/CNW¼SW¼" or footage from lines 100' SW of C SW SE

Lease Owner Brandt-Clark Oil Company

Lease Name Reinert Well No. 1

Office Address 505 First Nat'l Bank Bldg., Wichita, Ks. 67202

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed October 25, 1970

Application for plugging filed 19

Application for plugging approved 19

Plugging commenced October 25, 1970

Plugging completed October 25, 1970

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo F. Massey of Hays

Producing formation Depth to top Bottom Total Depth of Well 4435 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS — CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface Casing	0	0	451'	451'	-----

RECEIVED
STATE CORPORATION COMMISSION
OCT 28 1970
CONSERVATION DIVISION
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Heavy Mud from Total Depth to 660 Feet,
Plug and 50 sax Cement; Mud to 430 Feet,
Plug and 25 sax Cement; Mud to 40 Feet,
½ sax Hulls, Plug bridged w/Kelly and
10 sax Cement to Base of Cellar; 2 sax
Cement in Rat Hole. Job Completed at
8:15 P.M. on 10/25/70.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Allied Cementing Co., Inc.

Address 500 Bitting Building, Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

T. M. McCaul, Jr. of Sage Drilling Co. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) T. M. McCaul Jr.

500 Bitting Building, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 27th day of October, 1970.

Louise K. Whitted
Louise K. Whitted — Notary Public.

My commission expires November 26, 1970.

LOUISE K. WHITTED NOTARY PUBLIC SEDGWICK CO., KANS.

15.135.20380.0000

DRILLERS LOG

REINERT NO. 1

CASING RECORD:	OPERATOR:	Brandt-Clark Oil Co.	DESCRIPTION:
8-5/8" @ 451' w/300 sax cement	CONTRACTOR:	Sage Drilling Co.	100' SW of C SW SE Sec. 15-20S-23W Ness County, Kansas
TOTAL DEPTH: 4435'	COMMENCED:	October 16, 1970	
	COMPLETED:	October 25, 1970	ELEVATION: 2259KB

FORMATION	FROM	TO	REMARKS
Clay & Rock	0	65	
Rock & Blue Shale	65	452	
Shale	452	928	
Shale & Sand	928	1468	
Anhydrite	1468	1507	
Shale	1507	1600	
Shale & Shells	1600	2090	
Lime & Shale	2090	2865	
Shale & Lime	2865	3365	
Lime	3365	3478	
Lime & Shale	3478	3794	
Lime	3794	4070	
Lime & Shale	4070	4141	
Lime	4141	4288	
Lime & Shale	4288	4333	
Lime	4333	4435	D&A

RECEIVED
STATE CORPORATION COMMISSION
OCT 28 1970
CONSERVATION DIVISION
Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

SAGE DRILLING CO., INC.

By T. M. McCaul, Jr.

LOUISE K. WHITTED NOTARY PUBLIC SEDGWICK CO., KANS.

Subscribed and sworn to before me this 27th day of October, 1970.

Louise K. Whitted, Notary Public

My commission expires:
November 26, 1970.