

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15.135.30202.0000

AMENDED

TYPE OR PRINT
NOTICE: Fill out completely and return
to Cons. Div. office within 30 days.

API NUMBER None

LEASE NAME Petersilie A

WELL NUMBER 4

4290 Ft. from S/~~W~~ Line of Section (circle one)

2310 Ft. from E/~~N~~ Line of Section (circle one)

LEASE OPERATOR Kaiser-Francis Oil Company

SPOT LOCATION C - SW - NW - NE

ADDRESS P. O. Box 21468

SEC. 23 TWP. 20 S. RGE 24 (E) or (W)

CITY, STATE, ZIP Tulsa, OK 74121-1468

COUNTY Ness

PHONE#(918) 491-4314 OPERATORS LICENSE NO. 6568

Date Well Completed 4/27/66

Charater of Well Oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Date Plugging Commenced 10/18/95

Date Plugging Completed 10/30/95

The plugging proposal was approved on n/a (date)

by Steve Middleton (KCC District Agent's Name)

Is ACO-1 filed? On old form not, is well log attached? -

Producing Formation(s) Mississippi Depth to Top 4382 Bottom 4390 T.D. 4390

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULL OUT
Mississippi	Oil	4382	4390	8 5/8	259	None
				5 1/2	4382	1515

Described in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Dumped 2 sxs cmt on top of CIBP @ 4340'. Shot pipe @ 2000', 1700' & 1515'. Pulled csg up to 800' & pumped 50 sxs cmt & displaced it down w/6 sxs gel in wtr. Pulled csg to 300' & pumped 50 sxs cmt & displaced it down w/wtr. Finished pulling casing. Pumped 30 sxs cmt from 40' to surf. Topped off w/60 sxs cmt. Plugging complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Mike's Testing & Salvage, Inc.

License No. 31529

Address P. O. Box 209, Chase, KS 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Kaiser-Francis Oil Company

STATE OF Oklahoma COUNTY OF Tulsa, ss.

Charlotte Van Valkenburg (Employee of Operator or (Operator) of above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) C. Van Valkenburg

(Address) P. O. Box 21468, Tulsa, OK 74121-1468

SUBSCRIBED AND SWORN TO before me this 14th day of November, 19 95

Josh Ivloff
Notary Public

My Commission Expires: _____

RECEIVED
STATE CORPORATION COMMISSION

NOV 16 1995

CONSERVATION DIVISION
Wichita, Kansas Form CP-4
Revised 12-92

MY COMMISSION EXPIRES DEC. 23, 1997