

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado De'by Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15.135.30202.0000

LEASE NAME Petersilie A #4

WELL NUMBER 4

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

 Ft. from S Section Line

 Ft. from E Section Line

LEASE OPERATOR Kaiser-Francis Oil Company

SEC. 23 TWP. 20 RGE. 24 ~~MM~~ (W)

ADDRESS P.O. Box 21468 Tulsa, Ok. 74121

COUNTY Ness County

PHONE# (918) 491-4314 OPERATORS LICENSE NO. 6568

Date Well Completed 4-10-66

Character of Well Oil

Plugging Commenced 10-18-95

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 10-20-95

The plugging proposal was approved on (date)

by Steve Middleton (KCC District Agent's Name).

Is ACO-1 filed? if not, is well log attached?

Producing Formation Depth to Top Bottom T.O. 4390'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	259'	none
				5-1/2"	4382'	1515'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set
Dumped 2 sacks cement on CIBP @4340' Shot pipe @2000', 1700', 1518', Pulled up to 800' and pumped 50 sacks cement, displaced it down with 6 sacks gel in water. Pulled to 300', pumped 50 sacks cement, displaced it down with water. Pulled casing. Mix 30 sacks cement at 40 ft. and top off, (60/40 6% gel. Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 209 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Kaiser-Francis Oil Company

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

RECEIVED (Signature) Mike Kelso
STATE CORPORATION COMMISSION (Address) P.O. Box 209 Chase, Kansas 67524

SUBSCRIBED AND SWORN TO before me this 26th day of October, 19 95

11-2-95
Notary Public Irene Herzberg

My Commission Expires:

USE ONLY ONE SIDE OF EACH FORM

