

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Bldg.
 Wichita, Kansas 67202

WELL PLUGGING RECORD

Give All Information Completely
 Make Required Affidavit

COUNTY Pawnee SEC. 14 TWP. 20 RGE. 19 E/W
 Location as in quarters or footage from lines:
330' FSL 1420' FWL SW/4

Lease Owner Derrick-American Oil, Inc.
 Lease Name HAGERMAN Well No. #1
 Office Address 507 Insurance Bldg. Wichita, KS 67202
 Character of Well (Completed as Oil, Gas or Dry Hole): _____
 Date Well Completed 8-22-82
 Application for plugging filed 8-22-82
 Plugging commenced 8-22-82
 Plugging completed 8-22-82
 Reason for abandonment of well or producing formation _____

Locate Well
 correctly on above
 Section Platt.

Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Steve Durant
 Producing formation _____ Depth to top _____ bottom _____ T.D. 4320'
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out

Describe in detail the manner in which the well was plugged, indicating where the mud
 fluid was placed and the method or methods used in introducing it into the hold. If cement
 or other plugs were used, state the character of same and depth placed, from _____ feet
 to _____ feet for each plug set.

Bottom Plug: @ 840' w/70 sacks cement thru drill pipe(50/50 pozmix 4% gel 3% cc.)
Middle Plug: @ 360' w/40 " " " " " " " "
Top Plug: @ 40' w/ solid bridge
10 sacks in Rat Hole

(If additional description is necessary, use BACK of this sheet)
 Name of Plugging Contractor Lobo Drilling Co.

STATE OF Kansas COUNTY OF Barton, ss.
Ervin Neighbors (employee of owner) or (~~owner or operator~~) of the
 above-described well, being first duly sworn on oath, says: That I have knowledge of the
 facts, statements, and matters herein contained and the log of the above-described well as
 filed and that the same are true and correct. So help me God.

(Signature) Ervin Neighbors
Box 877 Great Bend, KS 67530
 (Address)

SUBSCRIBED AND SWORN TO before me this 1st day of Sept, 19 82

[Signature]
 STATE CORPORATION COMMISSION
 Notary Public.

My Commission expires: 4-29-86

SFP 0 2 1982

15.145.20988.0000

DRILLER'S WELL LOG

DATE COMMENCED: August 16, 1982
DATE COMPLETED: August 22, 1982

Derrick-American Oil, Inc.
HAGERMAN #1
330' FSL & 1420' FWL SW 1/4
Sec. 14, T20S, R19W
Pawnee County, Ks.

ELEVATION: 2224' K.B.

0 - 1354' Surface Soil, Red Bed, Shale, Sand
1354 - 1378' Anhydrite
1378 - 3685' Lime & Shale
3685 - 3733' Shale
3733 - 4183' Lime
4183 - 4302' Sand
4302 - 4320' Chert & Lime
4320' RTD

FORMATION DATA

Anhydrite 1354'
Haebner 3685'
Lansing K.C. 3733'
Cherokee 4183'
Mississippi 4302'
RTD 4320'

Surface Pipe? Set new 8-5/8",
20# pipe at 368' w/200 sacks
common, 2% gal, 3% cc.

A F F I D A V I T

STATE OF KANSAS
COUNTY OF BARTON) ss

Ervin Neighbors of lawful age, does swear and state that the facts and
statements herein are true and correct to the best of his knowledge.

Ervin Neighbors

Subscribed and sworn to before me this 27 day of August 1982.

My Comm. Expires:

4-29-86

Dorothy M. Wagne
Notary Public

RECEIVED
STATE CORPORATION COMMISSION

SEP 08 1982
CONSERVATION DIVISION
Wichita, Kansas