


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

WELL PLUGGING RECORD



Pawnee County. Sec. 14 Twp. 20S Rge. (E) 19 (W)
Location as "NE/CNW&SW¼" or footage from lines 1980' FS & 1980' FE lines
Lease Owner Continental Oil Company of sec. _____
Lease Name E. H. Hagerman "A" Well No. 1
Office Address Drawer 367, Plainville, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 4-20 1963
Application for plugging filed 4-20 1963
Application for plugging approved 4-20 (Verbal) 1963
Plugging commenced 4-20 1963
Plugging completed 4-20 1963
Reason for abandonment of well or producing formation No commercial zones encountered

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Mr. Eldon Petty
Producing formation None Depth to top _____ Bottom _____ Total Depth of Well 4267 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Cherokee Sand	Salt water	4158'	4201'	8 5/8"	367'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

The hole was mudded to 350 feet with a plug pushed to this depth. There was 35 sacks of cement spotted on the plug at 350 feet and the well mudded to 40 feet. A plug was pushed to 40 feet and the hole filled to surface with 15 sacks of cement.

RECEIVED
STATE CORPORATION COMMISSION

APR 25 1963

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Red Tiger Drilling Company
Address Wichita, Kansas

STATE OF Kansas, COUNTY OF Rooks, ss. L. E. Powell (employee of owner) or (owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

ARC
4-22-63
State CRW File
(Signature) L. E. Powell
Drawer 367, Plainville, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 22nd day of April, 1963

My commission expires 12-2-65
Kenneth J. Querry Notary Public.

DRILLERS LOG"A"
Hagerman No. 1

CASING RECORD: COMPANY: Contintental Oil Co. DESCRIPTION:
 8 5/8 @ 367' CONTRACTOR: Red Tiger Drilling Co. C NW SE
 w/200 sx cement COMMENCED: April 10, 1963 14-20S-19W
 Pawnee Co., Ks.
 ELEVATION: 2178 DF
 2181 RB

TOTAL DEPTH: 4267'

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Sod Shale	0	75	
Shale & Shells	75	523	
Red Bed	523	732	
Sand	732	870	
Shale & Shells	870	1315	
Anhydrite . . .	1315	1343	
Shale & Shells	1343	2360	
Lime & Shale	2360	2516	
Lime	2516	2600	
Lime & Shale	2600	3790	
Lime	3790	3895	
Lime & Shale	3895	4207	
Lime Shale & Sand	4207	4267	

RECEIVED
STATE CORPORATION COMMISSION

APR 25 1963

CONSERVATION DIVISION
Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

George A. Angle
George A. Angle

Subscribed and sworn to before me this 22nd day of April, 1963.

Melvin V. Head
Notary Public

My Commission Expires:

11-17-66

drs 4-24-63

State Corp. Comm.
Kansas Geological Society
CRW
File