

**Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas**

WELL PLUGGING RECORD

NORTE

**Locate well correctly on above
Section Plat**

Barton County. Sec. 32 Twp. 20 Rge. (E) 14 (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines

Lease Owner H. E. Alexander and Otto J. Kopke

Lease Name Potts Well No. 1

Office Address 2719 Forrest, Great Bend, Kans.

Character of Well (completed as Oil, Gas or Dry Hole) Dry hole

Date well completed 2-23-49 1949

Application for plugging filed 2-23 1949

Application for plugging approved. 2-23 19 49

Plugging commenced	2-23	19 49
--------------------	------	-------

Plugging completed.....	2-23	19 40
-------------------------	------	-------

Reason for abandonment of well or producing formation.....

If a producing well is abandoned, date of last production..... 19.....

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well..... C. D. Stough.....

Producing formation.....	Depth to top.....	Bottom.....	Total Depth of Well.....	Feet.....
--------------------------	-------------------	-------------	--------------------------	-----------

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

[illegible]

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from.....feet tofeet for each plug set.

Filled hole with heavy mud; set wood plug at 200'; cemented with 15 sac cement; set top plug at 30'; cemented with 10 sac cement.

RECEIVED
Conservation Div.
FEB 25 1943
STATE CORPORATION
COMMISSION
KANSAS

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to H. E. Alexander
Address 2719 Forrest, Great Bend, Kans.

STATE OF Kansas, COUNTY OF Barton, ss.
H. H. Alexander (employee of owner) or (owner or operator) of the above-described well


being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) H. E. Alexander
H. E. Alexander
2719 Forrest, Great Bend, Kansas
 (Address)

SUBSCRIBED AND SWORN to before me this 24 day of Feb., 1949

My commission expires 10-15-51 Notary Public.

22-5133-s 9-48-10M



15.009.00693.0000

WELL LOG

H.E. Alexander & Otto J. Kopke
Potts #1

Sec. 32; T-20; R-14W
SE/4 SE/4 NW/4
County: Barton

Total Depth: 3713'
Contractor: J.D. Ferrell Drilling Co., Inc.
Comm: 2-10-49 Comp: 2-23-49
Issued: 2-24-49 Rotary O-3713

Elevation: 1921' D.F.
Production: Dry

Casing Record: 872' cemented with 350 sax bulk
cement; cement circulated (8 5/8")

Figures indicate bottom of formations:

cellar	5
sand & shale	110
sand	150
shale	265
shale & shells	320
sand	390
red bed & shale	865
anhydrite	895
shale & red bed	1045
salt	1600
shale & shells	1650
lime & shale	2030
lime	2160
shale & shells	2300
lime & shale	3195
lime	3235
lime & shale	3540
lime	3599
lime & conglomerate	3625
lime & shale	3670
lime	3713
Total depth	3713

Tops:	
Top K.C.	3335
Base K.C.	3580
Conglomerate	3598
Simpson	3616
Arbuckle	3650
Total Depth	3713

We hereby certify this to be a correct and accurate log of the
above described well as shown by the daily drilling reports.

J.D. FERRELL DRILLING COMPANY, INC.


By:

J.W. Radlsback
J.W. Radlsback

Subscribed and sworn to before me this 24th day of February, 1949

My Commission Expires: 10-15-51

Merk V. Sandefur
Notary Public



RECEIVED

Conservation Div.

FEB 25 1949

STATE CORPORATION
COMMISSION
KANSAS