


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Barton County. Sec. 22 Twp. 20 Rge. 14 (E) W (W)  
Location as "NE/CNW/SW" or footage from lines SW SW NW  
Lease Owner Honaker-Davis Drlg. Co., et al  
Lease Name Potts Well No. 1  
Office Address 2008 Lakin, Great Bend, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 3-4 19 58  
Application for plugging filed 3-4 19 58  
Application for plugging approved 3-4 19 58  
Plugging commenced 9:00 a.m. 3-4 19 58  
Plugging completed 10:00 a.m. 3-4 19 58  
Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Don Truan  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3705 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	886	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with heavy rotary mud to 300 feet. Dumped in 1/3 sack hulls. Set Plug. Mixed 25 sacks cement by hand and poured same through drill pipe.

Filled hole with heavy rotary mud to 40 feet. Dumped in 1/3 sack hulls. Set Plug. Mixed 10 sacks cement by hand which filled hole to bottom of cellar.

RECEIVED  
STATE CORPORATION COMMISSION

MAR 6 1958

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor \_\_\_\_\_  
Address \_\_\_\_\_

STATE OF Kansas COUNTY OF Barton, ss.  
S. C. Lingreen (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) S. C. Lingreen  
Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 5th day of March, 1958

My commission expires 6-25-59  
Kenneth G. Fischer Notary Public.

PLUGGING  
FILE SEC 32T.20.R.146  
BOOK PAGE 87 LINE 12

DRILLERS' LOG

Potts No. 1  
 Loc: SW SW NW  
 Sec: 32-20S-14W  
 Barton County, Kansas  
 Company: Honaker-Davis Drlg. Co., et al  
 Contractor: Honaker-Davis Drlg. Co.

Comm: 2-24-58  
 Comp: 3- 4-58  
 Rotary Total Depth: 3705'  
 Casing: 8-5/8" at 886'  
 D & A.


0	40	Top soil & sand	
40	70	Clay	
70	190	Sand & Gravel	
190	315	Blue Shale	
315	405	Dakota Sand	
405	873	Red Bed & Shale	8 5/8" casing cemented at
873	915	Anhydrite	886' with 450 sacks cement
915	935	Red Bed & Shale	and 9 sacks calcium chloride.
935	1700	Shale & Shells	
1700	1900	Shale & Lime	
1900	3705	Lime & Shale	
3705		Total Rotary Depth	D & A

I certify that this is the true and correct copy of the  
 above log to the best of my knowledge.



H. S. Forbes

Subscribed and sworn to before me this 5th day of  
 March, 1958.



Kenneth G. Fischer, Notary Public

My commission expires: 6-25-59

RECEIVED  
 STATE CORPORATION COMMISSION

MAR 6 1958  
 CONSERVATION DIVISION  
 Wichita, Kansas

PLUGGING	
FILE	SEC. 32 T. 20 R. 14W
BOOK	PAGE 87 LINE 12