


WELL PLUGGING RECORD

BARTON County, Sec. 32 Twp. 20s Rge. 14w (X) (W)  
NE SE SE

Location as "NE/CNW/SW" or footage from lines  
Lease Owner PETROLEUM, INC.,  
Lease Name FREY "B" Well No. 1  
Office Address ROUTE 2, GREAT BEND, KANSAS  
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE  
Date well completed MARCH 30, 1963  
Application for plugging filed MARCH 30, 1963  
Application for plugging approved MARCH 30, 1963  
Plugging commenced MARCH 30, 1963  
Plugging completed MARCH 30, 1963  
Reason for abandonment of well or producing formation NO PRODUCIBLE FORMATIONS

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production NONE 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well DONALD TRUAN  
Producing formation --- Depth to top --- Bottom --- Total Depth of Well 3610 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	877'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet for each plug set.

MUDDED UP WITH HEAVY MUD TO 240' FOLLOWED BY 1/4 SACK HULLS AND WOODEN PLUG. PLACED 20 SACKS CEMENT THROUGH DRILL PIPE ONTO PLUG. MUDDED UP WITH HEAVY MUD TO 40', FOLLOWED BY 1/4 SACK HULLS, WOODEN PLUG AND 10 SACKS CEMENT TO BASE OF WELL CELLAR.

RECEIVED  
STATE CORPORATION COMMISSION

APR 4 1963

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor GARVEY DRILLING COMPANY  
Address ROUTE 2, GREAT BEND, KANSAS

STATE OF KANSAS, COUNTY OF BARTON, ss.  
DON SEARLE (employee of owner) or (~~MANAGER~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.  
DON SEARLE DIST. PROD. SUPT.  
(Signature) *Don Searle*  
ROUTE 2, GREAT BEND, KANSAS  
(Address)

SUBSCRIBED AND SWORN TO before me this 3RD day of APRIL, 19 63

My commission expires APRIL 14, 1967

*Arthur J. Wiles*  
Notary Public.



# WELL LOG

15.009.05286.0000

COMPANY Petroleum Inc

SEC. 32 T. 20S R. 14W

FARM Frey

NO. B-1

LOC. NE SE SE


TOTAL DEPTH 3610'

COUNTY Barton

COMM. 3-21-63

COMP. 3-30-63

CONTRACTOR Garvey Drilling Company



CASING 8 5/8" @ 877' w/450 sx

ELEVATION 1920' K.B.

PRODUCTION D & A

FIGURES INDICATE BOTTOM OF FORMATIONS

- 160' Sand and Gravel
- 315' Shale
- 375' Sand and Shale
- 425' Shale
- 490' Sand
- 785' Shale and Shells
- 842' Red Bed
- 868' Anhydrite
- 877' Shale and Shells
- 1280' Red Bed and Shale
- 1380' Shale and Shells
- 1525' Shale
- 1650' Shale and Lime
- 1860' Lime
- 2050' Lime and Shale Stks
- 2195' Lime
- 2380' Lime and Shale
- 2740' Shale and Lime Stks
- 3035' Shale and Lime
- 3178' Lime
- 3226' Lime and Shale
- 3304' Shale and Lime
- 3568' Lime
- 3600' Sand, Shale and Lime
- 3610' Lime
- 3610' RTD

**RECEIVED**  
STATE CORPORATION COMMISSION

APR 4 1963

CONSERVATION DIVISION  
Wichita, Kansas

State of Kansas }  
 County of Barton } SS

I, Sam N. Stephens of Garvey Drilling Company

upon oath state the above and foregoing is a true and correct copy of the log of the Frey B-1 well.

*Sam N. Stephens*  
 \_\_\_\_\_

Subscribed and sworn to before me this 1st day of April 1963

My Commission Expires: April 14th, 1967

*Arthur J. Miles*  
 \_\_\_\_\_  
 NOTARY PUBLIC