

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER _____

LEASE NAME Parkin #7

WELL NUMBER _____

SPOT LOCATION C NE NW

SEC. 10 TWP. 30S RGE. 18W (E) or (W)

COUNTY Kiowa

Date Well Completed _____

Plugging Commenced 1-16-85

Plugging Completed 1-22-85

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR K & E Drilling, Inc.

ADDRESS 100 S. Main Suite 300 Wichita, Ks. 67202

PHONE # (316 264-4301) OPERATORS LICENSE NO. 5266

Character of Well GAS
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? YES

Which KCC/KDHE Joint Office did you notify? Dodge City, Kansas

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom _____ T.D. 5040'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	502'	none
				4-1/2"	5038'	305'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.
Bottom perforations were already squeezed off with 95 sacks cement.

Shot casing @3423', 2018', 1524', 1021', 924', 722' and 305'. Pulled a total of 305' of 4-1/2" casing. Plugged surface with 2 hulls, 10 gel, and 175 sacks cement.

Plugging Complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050
Address P.O. Box 347 Chase, Kansas 67525

STATE OF Kansas COUNTY OF Rice, ss. STATE CORPORATION COMMISSION

R. Darrell Kelso (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) R. Darrell Kelso

(Address) Box 347 Chase, Ks. 67524

RECEIVED
1-30-85
JAN 30 1985

CONSERVATION DIVISION
Wichita, Kansas

SUBSCRIBED AND SWORN TO before me this 28th day of January, 19 85



Irene Hoover
Notary Public

My Commission expires: _____

DRILLER'S WELL LOG

OPERATOR: K & E DRILLING, INC.
719 Union Center
Wichita, Kansas 67202

WELL NAME: PARKIN #7
LOCATION: C NE NW
Sec. 10-30S-18W
Kiowa County, Kansas

CONTRACTOR: **K & E DRILLING, INC.**
719 UNION CENTER BLDG.
WICHITA, KANSAS

COMMENCED: October 18, 1967
COMPLETED: November 1, 1967
ELEVATION: 2171' Grd; 2177' D.F.
2180' K.B.
PRODUCTION: Gas

CASING RECORD:
8-5/8" @ 502' w/300 sx.
4 1/2" @ 5038' w/100 sx.
ROTARY TOTAL DEPTH: 5040'

FORMATION RECORD

Depths shown indicate bottom of formations encountered.

Shale	335
Sand	380
Shale	502
Shale & Shells	1858
Shale & Lime	2130
Lime	4980
Chert	4990
Lime	5040

RECEIVED
STATE CORPORATION COMMISSION
DEC 04 1967
CONSERVATION DIVISION
Wichita, Kansas

CERTIFICATION

State of KANSAS }
County of SEDGWICK } ss:

I, H. L. Wilson, of K&E DRILLING, INC., upon oath state that the above and foregoing is a true and correct copy of the Driller's Log of the above named well.

H. L. Wilson H. L. Wilson

Subscribed and sworn to before me this 7th day of November, 1967

Judie K. Eby
Judie K. Eby Notary Public.

My Commission Expires: 9-14-70

