


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Kiowa County, Sec. 10 Twp. 30 Rge. 18W E/W
Location as "NE/CNW 1/4 SW 1/4" or footage from lines
200' E C NE/4
Lease Owner Maurice L. Brown
Lease Name Parkin #1 Well No. _____
Office Address Wichita, Kansas 67202
Character of Well (Completed as Oil, Gas or Dry Hole) _____



Locate well correctly on above
Section Plat

Date Well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 12/2/76 _____ 19____
Plugging completed 12/4/76 _____ 19____
Reason for abandonment of well or producing formation
depleted.
If a producing well is abandoned, date of last production
_____ 19____

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Biberstein
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 5065'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	509	none
				4 1/2"	5063	578ft.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from _____ feet to
_____ feet for each plug set.

Sanded to 4900' and set 4 sacks cement. Loaded hole with water, shot pipe
at 942', 650', 584', pulled 18 joints. Set rock bridge at 240' and ran 25
sacks cement. Rock bridge 40 to 30' and ran 10 sacks cement.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION
12-14-76
DEC 14 1976

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor VOTH CASING PULLING
CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.
WALTER VOTH (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature) Walter Voth
CHASE, KANSAS
(Address)

SUBSCRIBED AND SWORN TO before me this 13th day of December, 19 76

Margaret Melcher
Notary Public.

My commission expires



DRILLER'S WELL LOG

OPERATOR: K & E Drilling, Inc.
719 Union Center
Wichita, Kansas

WELL NAME: #1 Parkin
LOCATION: 200' E of C NE/4
Sec. 10-30S-18W
Kiowa County, Kansas

CONTRACTOR: **K & E DRILLING, INC.**
719 UNION CENTER BLDG.
WICHITA, KANSAS

COMMENCED: August 27, 1965
COMPLETED: September 10, 1965
ELEVATION: 2203 KB
PRODUCTION: Gas

CASING RECORD: 8-5/8" @ 509'/350 sx.
4-1/2" @ 5062'/100 sx.

ROTARY TOTAL DEPTH: 5065'

FORMATION RECORD

Depths shown indicate bottom of formations encountered.

Clay and Shells	25
Sand	40
Shells & Shale	495
Anhydrite	545
Shale	1830
Shale & Lime	2495
Lime	3015
Shale & Lime	3265
Lime	3485
Lime & Shale	3549
Lime	5065

RECEIVED
K&E CO. FORMATION RECORDS
NOV 17 1973
11-17-74
CONSULTED BY
Wichita, Kansas

CERTIFICATION

State of KANSAS }
County of SEDGWICK } ss:

I, Wayne L. Brinegar, of K&E DRILLING, INC., upon oath state that the above and foregoing is a true and correct copy of the Driller's Log of the above named well.

Subscribed and sworn to before me this 16th day of September, 1965.
Wayne L. Brinegar
Wayne L. Brinegar

My Commission expires: 8-30-69
Judene M. Bannon
Judene M. Bannon Notary Public.

