

To: 1 090230
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

11-9 API NUMBER 15-097-21,214 0000 31p
N/2 NW SE, SEC. 11, T. 30 S, R. 18 W/E

TECHNICIAN'S PLUGGING REPORT
Operator License # 5171
Operator: Marathon Oil Company
Name & Address RR 1, Box 125
Medicine Lodge, KS 67104

2310 feet from S section line
1980 feet from E section line
Lease Name Kane G Well # 1
County Kiowa 162.50
Well Total Depth 5000 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 250

Abandoned Oil Well _____ Gas Well X Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Clarke Corporation License Number 5105
Address P.O. Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 1:30 p.m. Day: 9 Month: 11 Year: 19 92

Plugging proposal received from Elmo Morgenstern
(company name) Clarke Corporation (phone) 316-886-5665

were: 4 1/2" at 4999' w/100 sx cement, PBDT 4960', Perfs at 4895-4908, 4912-18, 4940-44'
1st plug sand back to 4845' and dump 4 sx cement on top of sand through bailer,
2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, and 150 sx
cement.

Plugging Proposal Received by Dan Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____
Operations Completed: Hour: 2:30 p.m. Day: 9 Month: 11 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug sanded back to 4845' and dumped 4 sx cement on top of sand
through bailer,
2nd plug pumped 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, and 150
sx cement.
Maximum pressure 150 and shut in 100 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Services. Recovered 3250' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
DATE 11-24-92
INV. NO. 36917

Signed [Signature]
(TECHNICIAN)