


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Kiowa County, Sec. 11 Twp. 30 Rge. 18 (W) (NW/SE)
Location as "NE/CNW/SW" or footage from lines _____
Lease Owner Messman-Ranehart Oil Company
Lease Name Kane Ranch Well No. #1-C
Office Address Box 66, Pratt, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed Yes 19____
Application for plugging approved Yes 19____
Plugging commenced 8-14 19 57
Plugging completed 8-18 19 57
Reason for abandonment of well or producing formation _____

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. M.A. Rives
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 5165 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2"		3,751'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Measured into TD 5165'.
Plugging started 8-14-57. Finished 8-18-57.
Plugged off bottom with sand to 4885' and dumped 5 sacks cement with bailer. Shot 5 1/2" casing at 3751'. Circulated mud and spotted oil.
Worked and started pipe. Plugged well with heavy mud to 300' and set permanent rock bridge. Dumped 20 sacks cement. Filled hole with mud to 35' and mixed 10 sacks for cap on well.

STATE OF KANSAS
8-21-57
ALICE J. 1957
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor J.O. Forbes d/b/a Forbes Casing Pulling Co.
Address Box 221, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
J.O. Forbes (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J.O. Forbes
Box 221, Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 20th day of August, 1957.

Patty J. Edman
Notary Public.

My commission expires November 8, 1960.

PLUGGING
FILE SEC 11 T. 30 R. 18 W
BOOK PAGE 32 LINE 43

NO. 1 KANE RANCH "C"Well Record

Location: NW SE Section 11-30S-18W
Kiowa County, Kansas

Operator: Messman-Rinehart Oil Company
518 Petroleum Bldg., Wichita, Kansas

Contractor: Messman-Rinehart Oil Company
518 Petroleum Bldg., Wichita, Kansas

Casing Record: 8 5/8" @ 393' w/225 sacks cement.

Commenced: June 14, 1957

Completed: July 7, 1957
(rotary)

Elevation: 2093 KB

Production:

* * * L O G * * *

Shale	40
Shale & shells	250
Shale-shells & Red Bed	380
Anhydrite	405
Red Bed & shale	430
Shale & Red Bed	760
Shale-Red Bed & Stks Anhydrite	1185
Shale-Red Bed & lime shells	1747
Shale-shells	2000
Shale & lime	2365
Lime	2565
Lime-shale	2655
Lime	2713
Lime-shale	3767
Lime	3819
Lime-shale	3882
Lime	3977
Lime-shale	4024
Lime	4085
Lime-shale	4397
Lime	4434
Lime & chert	4519
Lime	4796
Lime & shale	4901
Lime & chert	4970
Lime & shale	5054
Lime & chert	5160 R.T.D.

Electric log tops:

Heebner	4088 (-1995)
Br. Lime	4261 (-2168)
Lansing	4278 (-2185)
Cherokee	4816 (-2723)
Mississippi	4915 (-2822)

The undersigned, MESSMAN-RINEHART OIL COMPANY, hereby certifies that the above log is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Report.

MESSMAN-RINEHART OIL COMPANY

By: 

J. A. Gilliland

Subscribed and sworn to before me
this 8th day of July, 1957.

Elaine M. Malone
Notary Public

My Commission Expires: September 5, 1960

