


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Major Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Kiowa County. Sec. 16 Twp. 30S Rge. (E) 18 (W)
Location as "NE/CNWSW" or footage from lines C NE NW
Lease Owner Anadarko Production Company
Lease Name Schmidt "A" Well No. 1
Office Address Box 351, Liberal, Kansas 67901
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole
Date well completed 5/15 1968
Application for plugging filed 5/15 1968
Application for plugging approved 5/15 1968
Plugging commenced 5/15 1968
Plugging completed 5/15 1968
Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well R. J. Warren, Parish Hotel, Pratt, Kansas 67124
Producing formation Depth to top Bottom Total Depth of Well 5175 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	986'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole w/ mud to 490'. Pushed plug & formed bridge @ 490'.
Spotted 25 sacks of cement from 410' to 490'.
* Left hole open to surface for water well.
Plugged rat hole w/10 sacks of cement.
Completed @ 11:30 P.M. 5/15/68.

* Please refer to "Authorization" dated May 19, 1968, signed by landowner, Allen B. Schmidt.

RECEIVED
STATE CORPORATION COMMISSION
JAN 3 1969
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Leben Drilling Company
Address Great Bend, Kansas

STATE OF KANSAS COUNTY OF SEWARD, ss.
V. K. Downey (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God

V. K. Downey, Superintendent
Liberal Production Region

(Signature)


Box 351, Liberal, Kansas 67901
(Address)

Subscribed and sworn to before me this 31 day of December, 1968

J. W. Williams

Notary Public.

My Commission Expires April 28, 1971



COMPANY
 CONTRACTOR
 FARM
 LOCATION

Anadarko Production Company
 LEBEN DRILLING, INC.
 SCHMIDT A-1
 C NE NW Section 16-30S-18W
 KIOWA COUNTY, KANSAS
 5-3-68
 5-15-68

COMMENCED
 COMPLETED

0	20	Shale
20	110	Clay
110	140	Sand
140	190	Shale
190	250	Sand
250	510	Shale
510	540	Anhydrite
540	840	Shale
840	987	Shale and Lime
987	2345	Shale
2345	3220	Lime and Shale
3220	3895	Shale and Lime
3895	3978	Lime and Shale
3978	4300	Shale and Lime
4300	4450	Lime and Shale
4450	5175	Lime
	5175	RTD - D & A

RECEIVED
 STATE CORPORATION COMMISSION
 MAY 22 1968
 CONSERVATION DIVISION
 Wichita, Kansas

Set 8 5/8" New 24# Surface Casing - Set @ 986' with 450 sx Posmix w/200 sx common cement. Cement circulated.

I, Leslie Kite, do hereby certify that the above and foregoing is a true and correct copy of the log of the Schmidt A-1, located C NE NW of Section 16, Township 30S, Range 18 West, Kiowa County, Kansas, as reflected by the files of Leben Drilling, Inc.

Leslie Kite

 LESLIE KITE

STATE OF KANSAS)
) SS
 COUNTY OF BARTON)

Subscribed and sworn to before me, a Notary Public, in and for Barton County, Kansas, this 20th day of May, 1968.

Ulanda Nichols

 ULANDA NICHOLS, Notary Public

DRILLER'S LOG

WELL NAME: Schmidt "A" #1 ; COMPANY OPERATING: Anadarko Production Company
 ADDRESS of COMPANY: Box 351 Liberal, Kansas 67901
 WELL LOCATION: C $\frac{1}{4}$ NE $\frac{1}{4}$ NW $\frac{1}{4}$,
4620 ft. North of South line,
1980 ft. East of West line: Sec. 16, Twp. 30S, Rge. 18W, Kiowa County, Kansas
 DRILLING STARTED 5/3, 1968; DRILLING COMPLETED 5/15, 1968
 WELL COMPLETED , 19 ; WELL CONNECTED , 19
 ELEVATION: 2241.2 ft. Ground Level; CHARACTER OF WELL (Oil, Gas, or Dry Hole) Dry Hole

OIL OR GAS SANDS OR ZONES - PERFORATIONS - ACIDIZING AND FRACTURING INFORMATION					
Name	From	To	No. of Shots	Gallons Used	Kind Used

CASING RECORD

Size	Amount Set	Sacks of Cement	Amount Pulled
8-5/8"	986'	650	None

FORMATION RECORD

Formation	Top	Bottom	Formation	Top	Bottom
Surface Sand	0'	20'			
Anhydrite & Clay	20'	190'			
Sand	190'	250'			
Shale	250'	1630'			
Shale & Lime	1630'	2345'			
Lime & Shale	2345'	2750'			
Lime	2750'	2886'			
Lime & Shale	2886'	3220'			
Shale & Lime	3220'	3895'			
Lime & Shale	3895'	3978'			
Shale & Lime	3978'	4450'			
Lime	4450'	5175'			
R.T.D.	5175'				

RECEIVED
 STATE CORPORATION COMMISSION
 MAY 22 1968
 CONSERVATION DIVISION
 Wichita, Kansas

RESULTS of INITIAL PRODUCTION TEST: Plugged & Abandoned on 5/15/68