

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 124-14

LOCATION NE-NE-NE

SEC. 1 TWP. 20 RGE. 11-w

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease L. A. Stechel

Operator Gulf Oil Corp. Address Box #661 Tulsa, Okla.

Field _____ County Butler

Total Depth 3284 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 13" - 161 ft. Circulated with cement
7" casing set at 3265 ft. - 100 sacks of cement. Plugged
back to 3260 ft with chat - Dumped 6 sacks of cement
at 3260 ft. - Capped off & Pulled the 7" casing - and
to 160 ft. Set Rock Bridges & 15 sacks of cement at 160 ft.
and to 30 ft. - Bridge & 10 sacks of cement
at the surface.

Skull Casing Pulling Co. Plugging Contractors

PLUGGING RECEIVED
FILE SEC. 1 T. 20 R. 11-w
BOOK PAGE 124-14
DEC 15 1951

C. D. Stouck
District Conservation Agent
Date 12-13-51

CONSERVATION DIVISION
Wichita, Kansas
12-1551