

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 34-34LOCATION NE-NW-NESEC. 1 TWP. 20 RGE. 11-WDry Hole Abandoned Oil Well X Abandoned Gas Well

I have today completed supervision of plugging of:

Well No. 5 Lease Fred StechelOperator Magnolia Petrol. Co Address Box #770 - S. Bend. Kans.Field County BartonTotal Depth 3277 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 12 1/2 - 202 ft. Circulated with cement.
7" casing set at 3205 ft. Plugged back to 3117 ft.
with cement. Filled with shot from 3117 ft. to 3100 ft.
Dumped 6 sacks of cement at 3100 ft. Shot off & pulled
the 7" casing. Mud to 202 ft. Set Rock Bridge
& 25 sacks of cement at 202 ft. Mud to 30 ft.
Bridge & 10 sacks of cement at the surface.
Bob Mullins - Plugging Completed

STATE CORPORATION COMMISSION

OCT. 25 1950

10-25-50

CONSERVATION DIVISION

Wichita, Kansas

District Conservation Agent

Date 10-23-50

PLUGGING			
FILE	SEC. <u>1</u>	T. <u>20</u>	R. <u>11W</u>
BOOK	PAGE <u>30</u>	LINE <u>34</u>	