

15.135.20016.0000

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

MAR 13 1967
3-13-67
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Leben Drilling Inc. Et Al

Complete Address: 815 Wichita Plaza Wichita, Kansas

Lease Name Petersilie "B" Well No. 1

Location C SE NW Sec. 23 Twp. 20 Rge. 24 (E) (W) X

County Ness Total Depth 4400

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Co. Tools

Address: License No.

Operation Completed: Hour 4:30 A Day 12 Month 3 Year 1967

The Above well was plugged as follows:

RTD 4400' 8 5/8 csg set at 274' cwc 185 sc.

Gunned pits, circulated heavy mud, set cementing plug at 540' and displaced 25 sc cem.

thru drill pipe. Heavy mud to 260' set cementing plug and displaced 20 sc cement thru

drill pipe. Heavy myd to 40' set cementing plug, 1/2 sc hulls and 8 sc cement to base

of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 3/13/67

INV. NO. 4892-67

Signed: Leo J. Massey
Well Plugging Supervisor