

15.145.19005.0000

Form GP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

STATE CORPORATION COMMISSION
FEB 18 1963
2-18-63
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Continental Oil Co
Complete Address: Box 98 Plainville, Kansas
Lease Name Hagerman Well No. 1
Location GSW SW Sec. 14 Twp. 20 Rge. (E) (W) 19
County Pawnee Total Depth 4300
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated:
Plugging Contractor: Knight Casing Pulling
Address: Chase, Kansas License No. 436
Operation Completed: Hour 10AM Day 14 Month 2 Year 63

The Above well was plugged as follows:

8 5/8" 373' circulated with cement - 4 1/2" 4299' with 200 sax cement - PB 4222'
Perforated 4213' - filled with sand to 4200', set 3 sax cement with dump
bailer - pulled 3300' 4 1/2" to 565', circulated hole with heavy mud through
4 1/2" at 565' (35 sax cel), displaced 25 sax cement through 4 1/2" at 375', heavy
mud to 35', set bridge and filled to bottom cellar with cement.

Mudding and cementing by Knight Company pump truck.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: E. J. Letty
Well Plugging Supervisor

DATE 2/18/63
INV. NO. 6595-U