

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
DEC 07 1976 12-7-76
(of this well)
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - -

Operator's Full Name Maurice L. Brown

Complete Address 1500 Vickers KSB&T Bldg Wichita, KS

Lease Name Parkin Well No. 1

Location 200' E C NE Sec. 10 Twp. 30 Rge. 18 (E) (W) W

County Kiowa Total Depth 5065

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Voth Casing Pulling Co

Address 715 S. Ave A Arkansas City, KS License No. 684

Operation Completed: Hour 3:00 PM Day 4 Month 12 Year 1976

The above well was plugged as follows:

509 ft 8 5/8 surface cemented with 350 sacks. 5062 ft 4 1/2 long string
cemented with 100 sacks. Top perf. 4991 ft. Sand to 4900 ft, 4 sacks
cement with bailer. Pulled 580 ft 4 1/2. Set 10 ft rock bridge at
260 ft., with 25 sacks cement. Mud to 40 ft, plug, 10 sacks cement
to surface.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 12-7-76
INV. NO. 4286-w