

 KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Well Plugging Authority,  
issued September 26, 1967.

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 18 1967  
12-18-67  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Graham-Michaelis Drilling, Inc.

Complete Address: 211 N. Broadway, Wichita, Kansas 67202

Lease Name Kane Well No. # 1-14

Location C NE SE Sec. 14 Twp. 30 Rge. 18 (E) (W)W

County Kiowa Total Depth 5083'

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Southwest Casing Pulling Company

Address: Box 364, Great Bend, Kansas 67530 License No. 399

Operation Completed: Hour 12:30PM Day 14th Month December Year 1967

The Above well was plugged as follows:

468' of 8 5/8" surface pipe, cemented with 300 sacks. 5011' of 5 1/2" long  
string, cemented with 75 sacks. This is an open hole. Bottom of the hole  
was sanded to 5000', and cemented with 5 sacks, through the dump bailer,  
with cement from 5000' to 4960'. 4200' of 5 1/2" long string was recovered  
from the hole. Fluid in the hole was bailed down to 325', bridge plug and  
rock and sand bridge from 325' to 300', hole was filled with 4 yards of  
ready-mix cement, with cement from 300' to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Audie Elving  
Well Plugging Supervisor

INVOICED

DATE 12/18/67

INV. NO. 6936-W