

KANSAS

*AL*

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 30 1972  
5-30-72  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Graham Michaelis Corp.

Complete Address 211 N Broadway Wichita, Ks

Lease Name Smith Well No. 1-21

Location C SW/NW Sec. 21 Twp. 30 Rge. 18 (E) (W) W

County Kiowa Total Depth 5130

Abandoned Oil Well        Gas Well X Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Southwest Casing Pulling Co. Inc.

Address Box 364 Great Bend, Ks License No. 399

Operation Completed: Hour 10:30 AM Day 27 Month 5 Year 1972

The above well was plugged as follows:

640 ft 8 5/8 surface pipe cemented with 400 sacks. 5129 ft 4 1/2 long

string cemented with 125 sacks. Top perf. 5047 ft. Sand back to

5000 ft, 4 sacks cement with bailer. Pulled 4140 ft 4 1/2. Set 20 ft

rock bridge at 320 ft. Fill hole with 5 yds redimix to surface.

      

      

      

      

I hereby certify that the above well was plugged as herein stated.

Signed: *A. Russell Biberstein*  
Well Plugging Supervisor

INVOICED  
DATE 5/31/72  
INV. NO. 5772-W