

KANSAS

FORM CP-3
Rev. 1-8-82

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Oil Property Management

Complete Address 221 North Main Suite 200 Wichita Kansas 67202

Lease Name View Well No. 1

Location C-NE-NW Sec. 24 Twp. 30 Rge. 18 (East)(West)

County Kiowa Total Depth 5155'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor George Nicholas Casing Pulling

Address Box 873, Geneseo, Kansas 67444 License No. 711

Operation Completed: Hour: 5:15 P.M. Day: 5 Month: Aug Year: 19 82

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

They ran 5153' of 4 1/2" production pipe & plugged it back to 3802'. They perforated it from 3622' to 3728'. 1st plug sanded bottom back to 3600' & dumped 4 slbs of cement on top of it with Baler. 2nd plug jumped through head on 8 5/8" surface casing. They jumped 5 slbs hulls & 25 slbs gell & released rubber plug followed it with 250 slbs of cement. The plugging was accomplished by Dowell Cementing Co.

Amount of Surface Casing: 510' of 8 5/8"

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Paul A. Luttin
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

RECEIVED
STATE CORPORATION COMMISSION
8-10-82
AUG 10 1982
CONSERVATION DIVISION
Wichita, Kansas

Signed: _____
Conservation Division Agent
INVOICED
DATE 8-18-82
INV. NO. 901-W