

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

MAY 27 1975
5-27-75
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Shawn of Sage Drlg Co has this

date requested permission to plug the following described well:

Mr. Shawn guarantees payment of the plugging fee.

Operator's full Name: Maurice L. Brown & I. Wayne Woolsey

Complete Address: 1500 Vickers KSB&T Bldg Wichita, KS

Lease Name: Hantla A Well No. 1

Location: C N/2 NE Sec. 25 Twp. 30S Rge. 18 (E)(W)W

County: Kiowa Total Depth 5150 Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Shawn was instructed to plug the well as follows:

512 ft 8 5/8 surface cemented with 400 sacks. Pump plug,

35 sacks cement to 300 ft. Mud to 40 ft, plug, 1/2 sack hulls,

15 sacks cement to surface. 2 sacks cement in rat hole.

Pumped by Halliburton Cementing Great Bend, KS

Very truly yours,

Conservation Division Agent