

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
MAR 5 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Hanna of Anadarko Production Co has this
date requested permission to plug the following described well:

Mr. Hanna guarantees payment of the plugging fee.

Operator's full Name: A nadarko Production Co

Complete Address: Box 351 Liberal, KS

Lease Name: Smith J Well No. 1

Location: 660' FS & WL of Sec. 31 Twp. 30s Rge. 18 (E)(W) W

County: Kiowa Total Depth 500' Oil Well

Gas Well Input Well SWD Well D & A Skid Rig
Lost Hole X

Mr. Hanna was instructed to plug the well as follows:

Drilled 12 1/4 surface hole to 500 ft. Lost circulation. - Set
10 ft rock bridge at 300 ft, 40 sacks cement. Mud to 40 ft,
plug, 1/2 sack hulls, 20 sacks cement to surface. 2 sacks
cement in rat hole. Skid rig 250' north.

Pumped by Sun Cementing Co Great Bend, KS

Very truly yours,

Conservation Division Agent

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027

3830 S. Meridian

WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
MAR 20 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Hanna of Anadarko Production Co has this date requested permission to plug the following described well:

Mr. Hanna guarantees payment of the plugging fee.

Operator's full Name: Anadarko Production Co

Complete Address: Box 351 Liberal, KS

Lease Name: Smith J Well No. 1-A

Location: 250' N of 660' FS & WL Sec. 31 Twp. 30s Rge. 18 (E)(W) W

County: Kiowa Total Depth 5230 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Hanna was instructed to plug the well as follows:

407 ft 8 5/8 surface cemented with 400 sacks. Pump plug.

40 sacks cement to 400 ft. Mud to 40 ft, plug, 1/2 sack

hulls, 20 sacks cement to surface. 2 sacks cement in rat hole.

Pumped by Sun Cementing Co Great Bend, KS

Very truly yours,

Russell B. Bihurst
Conservation Division Agent