

State of Kansas



FORM - CP-2
Rev. 9-8-64

15.135.30243.0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Pfannenstiel of Leben Drlg. Co. has this date requested permission to plug the following described well:

Mr. Pfannenstiel guarantees payment of the plugging fee.

Operator's full Name: Leben Drilling Inc.

Complete Address: 815 Wichita, Plaza Wichita, Kansas

Lease Name: Pember Well No. 1

Location: C SNW SE Sec. 23 Twp. 20 Rge. 24 (E)(W) X

County Ness Total Depth 4437 Oil Well

Gas Well Input Well SWD Well D & A XLost Hole

Mr. Pfannenstiel was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 540'
and displace 30 sc cement thru drill pipe. Heavy mud to 250' set
cementing plug and displace 20 sc cement thru drill pipe. Heavy
mud to 40' set cementing plug 1/3 sc hulls and 10 sc cement to
base of celler. Plug rat hole with 2 sc cement.

RECEIVED
STATE CORPORATION COMMISSION

Very truly yours,

SEP 6 1966

Leo Massey
Conservation Division Agent
Wichita, Kansas