

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
OCT 25 1960
10-25-60
CONSERVATION DIVISION
WICHITA, KANSAS

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Paul Gatlin of Anadarko Production Co. has this date requested permission to plug the following described well:

Mr. Gatlin guarantees payment of the plugging fee.

Operator's full Name: Anadarko Production Company

Complete Address: P. O. Box 351, Liberal, Kansas

Lease Name: Emerson "A" Well No. # 1

Location: 1980' FSL & 1250' FW Sec. 16 Twp. 30 Rge. 18 (E)(W) W

County Kiowa Total Depth 5188' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Gatlin was instructed to plug the well as follows:

1030' of 8 5/8" surface pipe, cement circulated with 650 sacks. Push plug to 1000', and cement with 25 sacks. Push plug to 300', and cement with 25 sacks. Mud to 40', bridge with hulls, and cement with 10 sacks to base of cellar. Bridge and cement rat hole with 2 sacks.

These plugging orders were given bt Gilbert Toman

Very truly yours,

Archie Elving
Conservation Division Agent