

State of Kansas



JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

29 December 1981

VERBAL PERMIT FORM (To be filed by Plugging Agent)

Dear Sir:

Mr. Elmo Morgenstern of Clark Corporation has this date requested permission to plug the following described well:

Operator's Full Name: The Maurice L. Brown Co.

Complete Address: Box 11320 Kansas City Mo. 64112

Lease Name: Wicklow Well No. 1

Location: C-NE-NE Sec. 16 Twp. 30 S Rge. 18 1/2 (E) (W)

County: Kiowa Total Depth: 5150'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: ~~_____~~

Mr. Morgenstern was instructed to plug the well as follows:

There is 548' of 8 1/2" surface casing cement annulated. There is 5108' of 5 1/2" production pipe cemented. They plugged the well back to 5066'. The perforations were from 4486' to 4492'. Last plug sand back bottom to 4450' then put 3 sbs of cement on top of sand. In by plug pumped down 5 sbs well 5 sbs pull 5 sbs. Job then released rubber plug and pumped 200 lbs cement on top of it. They recovered 3192' of 5" production pipe. The plugging was accomplished by Halliburton Co. common cement. Shut in at 500# pressure.

Very truly yours,

RECEIVED
STATE CORPORATION COMMISSION

Paul Smith
Conservation Division Agent
Wichita, Kansas

JAN 19 1982