


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Barton County. Sec. 34 Twp. 20S Rge. 12W (E) (W)  
Location as "NE/CNW%SW%" or footage from lines 745' FNL & 330' FEL of NE/4  
Lease Owner Kewanee Oil Company  
Lease Name Lang Well No. 6  
Office Address Box 360, Hoisington, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Oil  
Date well completed March 16, 19 52  
Application for plugging filed October 9, 19 59  
Application for plugging approved October 12, 19 59  
Plugging commenced October 15, 19 59  
Plugging completed November 2, 19 59  
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production July 19 59  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Donald Truan, Russell, Kansas  
Producing formation Arbuckle Depth to top 3383 Bottom 3399 Total Depth of Well 3400 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Heebner	Dry	3008		8-5/8"	246	None
Brown Lime	Dry	3136		5-1/2"	3384	2705
Lansing	Dry	3151				
Arbuckle	Oil	3383	3400			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Measured into Total depth 3400'. Sanded back to 3370'  
and dumped 5 sacks of cement. Shot and pulled casing.  
Squeezed well with 15 sacks of mud and 80 sacks of cement.  
Capped well with 5 sacks of cement.

STATE CORPORATION COMMISSION  
NOV 16 1959  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Forbes Casing Pulling Company  
Address Box 221, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.  
Peter Blanda (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Peter Blanda  
Box 360, Hoisington, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 10th day of November, 1959

My commission expires September 21, 1959  
Samuel W. Fuller  
Notary Public.



## KEWANEE OIL COMPANY

WELL RECORD: Lang #6

Elevation: 1827' C.M.

Location: 745' from North line and 330' from East line of NE/4 Section  
34, T-20-S, R-12-W, Barton County, Kansas.

Drilling Commenced: February 21, 1952.

Drilling Completed: March 16, 1952.

Total Depth: 3400' C.M.

FBTD: 3399' C.M.

Treating Record: Acidized with 1000 gal Type "J" 15% on 3-10-52.  
Acidized with 2000 gal Type "J" 15% on 3-12-52.

Initial Production: Pumped 71.58 bbls. oil and 170 bbls. water in 23½ hrs.

Lane Wells Tops

Heebner shale	3008 (-1181)
Brown Lime	3136 (-1309)
Lansing-K.C.	3151 (-1324)
Arbuckle dolomite	3383 (-1556)

Casing Record8-5/8" OD casing set at 245.58' C.M. and cemented w/ 200 sacks 3% gel.  
5-1/2" OD casing set at 3383.68' C.M. and cemented w/ 100 sacks.Formation Record

0	Surface
236	Sand and clay
253	Red rock
553	Red rock and shale
605	Anhydrite
1080	Shale and shells
1390	Shale, shells and slate
1440	Shale and shells
1814	Shale and lime
1837	Lime
2862	Shale and lime
3035	Lime
3224	Shale and lime
3385	Lime