


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Barton County. Sec. 34 Twp. 20S Rge. 12 (X) W (W)

Location as "NE/CNW/SW" or footage from lines SE SE NW  
Lease Owner The Vickers Petroleum Co., Inc.  
Lease Name Zirnich Well No. 1  
Office Address 610 Union Center - Wichita 2, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Oil  
Date well completed February 9 19 49  
Application for plugging filed November 5 19 57  
Application for plugging approved November 5 19 57  
Plugging commenced November 6 19 57  
Plugging completed November 11 19 57  
Reason for abandonment of well or producing formation Oil Depleted



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production May 21 19 57  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Don Truan, Route 1, Russell, Kansas  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3415 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	252'	None
				5 1/2"	3398'	2698'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plugged back with crushed rock to 3278'. Dumped 5 sx. cement @ 3278' with dump bailer. Top of cement 3240'. Filled hole with mud to 250' Set rock bridge, dumped 25 sx. cement. Top of cement 175'. Filled hole with mud to 40', set rock bridge, dumped 10 sx. cement for cap.

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Miller Casing Pulling Co. License No. 12  
Address Great Bend, Kansas

STATE OF Kansas COUNTY OF Sedgwick, ss.  
H. L. Peel (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) H. L. Peel  
610 Union Center, Wichita 2, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 15th day of November, 19 57

My commission expires August 13, 1961 Allen Denton Notary Public.

RECEIVED  
STATE CORPORATION COMMISSION

NOV 16 1957

CONSERVATION DIVISION  
Wichita, Kansas

PLUGGING  
FILE SEC 34 T 20 R 12 W  
BOOK PAGE 59 LINE 15

## THE VICKERS PETROLEUM CO., INC.

Zirnich Well #1  
SE SE NW 34-20S-12W  
Barton County, Kansas

Casing Record:  
8-5/8" @ 252' w/175 sx  
5 1/2" @ 3398' w/100 sx

Commenced: January 13, 1949  
Completed: February 9, 1949

Elevation: 1838' R. B.  
Potential: 291 B.O.P.D. no water

L O G

Sand	0-190
Shale	190-240
Shale & Shells	240-252
Red Bed & Red Rock	252-450
Red Bed	450-615
Anhydrite	615-640
Shale & Shells	640-1040
Salt & Shale	1040-1310
Shale & Lime	1310-1515
Lime Broken	1515-1760
Lime & Sand	1760-1825
Lime Broken	1825-2055
Lime & Shale	2055-2440
Shale & Lime	2440-2585
Lime & Shale	2585-2625
Lime	2625-3080
Shale & Sand	3080-3148
Lime	3148-3377
Shale	3377-3396
Dolomite	3396-3403 R.T.D.

Cable Tools:  
Drill Deeper 3403-3415 T.D.

Oil 3411-3415  
Fill up 2700' over night  
Swab down 72 bbl. & Swab 8 bbl. per hour for 4 hrs.  
Acidize w/1000 gal. No help

Tops:	
Heebner	3020
Brown Lansing	3148
White Lansing	3164
Arbuckle	3396

I hereby certify that this log is true and correct to the best of my knowledge and belief.

THE VICKERS PETROLEUM CO., INC.

By H. C. Paris

Subscribed and sworn to before me  
this 8th day of March, 1949.

Allen P. Denton  
Notary Public

My commission expires August 13, 1949.

