


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above Section Plat

Barton County. Sec. 33 Twp. 20 Rge. 12 (E) (W) W
Location as "NE/CNW/SW" or footage from lines SW NW NW
Lease Owner L. K. Parrish & C-G Drilling Co.
Lease Name Churchill Well No. 1
Office Address Fourth National Building, Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed December 5 1960
Application for plugging filed December 5 1960
Application for plugging approved December 5 1960
Plugging commenced December 5 1960
Plugging completed December 5 1960
Reason for abandonment of well or producing formation Too low structurally

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3536 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS				CASING RECORD		
FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	285'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.


Filled hole with heavy mud to 270'. Set plug. Put in 1/4 sack hulls and 25 sacks cement. Filled with heavy mud up to 35'. Set plug. Filled to top with 1/2 sack hulls and 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
12-9-60 DEC 9 1960
CONFIDENTIAL

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor C-G Drilling Co.
Address 107 Rule Building, Wichita 2, Kansas

STATE OF KANSAS COUNTY OF SEDGWICK, ss.
G. F. Galloway (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.
(Signature) G. F. Galloway
107 Rule Building
(Address)

SUBSCRIBED AND SWORN to before me this 7th day of December, 1960.



Vicky Jacobs
Notary Public.

15.009.06973.0000

W E L L L O G

OPERATOR L. K. Parrish and C-G Drilling Co. SEC. 33-20-12W
 WELL NAME Churchill #1 LOC. SW ^{NW} NW
 TOTAL DEPTH 3536' COUNTY Barton
 COMM. November 26, 1960 COMP. December 5, 1960 STATE Kansas
 RIG NO. 2 ELEVATION 1856' K.B.
 CASING: Ran 285' (14 jts.) 8-5/8" OD Surface Casing. PRODUCTION: D & A

All measurements taken from the top of rotary bushing.

FROM	TO	FORMATION	DEVIATION FROM VERTICAL	REMARKS:
0	219	Sand		
219	639	Red Bed		
639	672	Anhydrite		
672	1445	Shale-Shell		
1445	2650	Lime-Shale	0° - 2500	
2650	2810	Shale-Lime	0° - 2750	
2810	3050	Lime-Shale	0° - 3000	
3050	3536	Lime	0° - 3250 0° - 3500	

RECORDED
 STATE COMMISSION
 DEC 9 1960
 CONF. DIVISION
 Wichita, Kansas

STATE OF KANSAS }
 COUNTY OF SEDGWICK } SS.

The undersigned hereby certifies that to the best of his knowledge and belief, the above facts are true and correct.

C-G DRILLING CO.

By G. F. Galloway
G. F. Galloway

SUBSCRIBED AND SWORN TO, BEFORE ME, THIS 7th day of December, 1960.

My commission expires:
May 20, 1963

Vicky Jacobs
Vicky Jacobs - Notary public

