

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH

	33		

Locate well correctly on above
Section Plat

Barton County, Sec. 33 Twp. 20 Rge. 12 (E) W (XX)
Location as "NE/CNW&SW&" or footage from lines. NE NE SE
Lease Owner Duke Drilling Company
Lease Name Kasselman Well No. 4
Office Address P. O. Box 123, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry
Date well completed December 23, 19 59
Application for plugging filed December 23, 19 59
Application for plugging approved _____ 19 ____
Plugging commenced December 23, 1959 19 59
Plugging completed December 23, 19 59
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production _____ 19 ____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Don Truan

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3472 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

RECEIVED
STATE CORPORATION COMMISSION
DEC 30 1959
CONSERVATION DIVISION
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud to 270'. Set 1/4 sack hulls & 25 sacks cement. Filled hole to 40" with heavy mud. Set 1/4 sack hulls & 10 sacks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor _____

Address _____

STATE OF Kansas, COUNTY OF Barton, ss.

C. M. Olson

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Cecil M Olson

P. O. Box 123, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 28th day of December, 19 59

My commission expires June 24, 1963

Clair E. Stimson
Notary Public.



WELL LOG

Date Commenced
Date Completed

December 13, 1959
December 23, 1959

Duke Drilling Company
Kasselman #4
NE NE SW Section 33-20-12
Stafford County, Kansas

0' - 180'	Surface Sand
180' - 276'	Red Bed
276' - 613'	Red Bed
613' - 640'	ANHYDRITE
640' - 1130'	Shale and Shells
1130' - 1285'	Salt and Shale
1285' - 1430'	Shale and Shells
1430' - 1785'	Shale and Lime
1785' - 2260'	Lime and Shale
2260' - 2765'	Lime and Shale
2765' - 2915'	Lime
2915' - 3032'	Lime
3032' - 3036'	Shale HEEBNER
3036' - 3050'	Lime and shale
3050' - 3064'	Lime TORONTO
3064' - 3159'	Shale DOUGLAS
3159' - 3174'	Lime and Shale IATAN
3174' - 3400'	Lime and Shale
3400' - 3416'	CONGLOMERATE
3416' - 3448'	Dolomite shale chert. ARBUCKLE
3448' - 3472'	Dolomite
3472'	RTD

Elevation 1835RB

Anhydrite	613	-1222
Heebner	3032	-1197
Toronto	3050	-1215
Douglas	3064	-1229
Iatan	3159	-1324
Lansing	3174	-1339
Conglomerate	3400	-1565
Arbuckle	3416	-1581
RTD	3472	-1637

Casing 8 5/8" set @ 276'
with 190 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION

DEC 30 1959

CONSERVATION DIVISION

AFFIDAVIT

State of Kansas County of Barton

I, Lewis O. Chubb, Geologist, do swear that the statements and
matters herein contained are true to the best of my knowledge.

THE DUKE DRILLING COMPANY

By: L. O. Chubb
Geologist

Subscribed and sworn to before me this 29th day of December, 1959

John E. Hemison
Notary Public

My Commission Expires: June 24, 1963.