


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Barton County, Sec. 33 Twp. 20 Rge. 12 (E) (W)
Location as "NE/CNW&SW&" or footage from lines SW NW SE
Lease Owner Duke Drilling Company
Lease Name Kasselmann Well No. 3
Office Address Box 123, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 9-29 19 56
Application for plugging filed 9-29 19 56
Application for plugging approved 9-29 19 56
Plugging commenced 9-29 19 56
Plugging completed 9-29 19 56
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Russell Brundege
Producing formation Depth to top Bottom Total Depth of Well 3446 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	253'	8 5/8	253'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud to 240'. Set bottom plug with 1/3 sack hulls wrapped tight in sack and 20 sacks cement. Heavy mud to 35'. Set top plug with 1/3 sack hulls and 10 sacks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Duke Drilling Company
Address Box 123, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
Cecil M. Olson (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Cecil M. Olson
Box 123, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 29 day of September, 1956

My commission expires June 24, 1959

Chas. E. Stevenson
Notary Public.

PLUGGING
FILE SEC 33 T. 20 R. 12W
BOOK PAGE 104 LINE 7

RECEIVED
STATE CORPORATION COMMISSION
OCT 2 1956
10-4-56
CONSERVATION DIVISION
WICHITA, KANSAS

WELL LOG

Date Started: 9-20-56
Date Completed: 9-29-56

Kasselman No. 3
SW NW SE
Sec. 33-20-12
Barton County, Kansas

Elevation 1844 K.B.
Anhydrite 620' (-1224)
Heebner 3034' (-1190)
Brown Lime 3160' (-1316)
Lansing 3177' (-1333)
Conglomerate 3398' (-1554)
R.T.D. 3446' (-1602)
No Arbuckle

0' - 210' Sand and Shale
210' - 620' Red Bed
620' - 659' Anhydrite
659' - 755' Shale and Shell
755' - 1605' Shale and Shell
1605' - 2040' Lime and Shale
2040' - 2570' Lime and Shale
2570' - 2810' Lime and Shale
2810' - 3034' Lime
3034' - 3105' Heebner
3105' - 3177' Lime
3177' - 3285' Lansing
3285' - 3398' Lime
3398' - 3446' Conglomerate
3446' R.T.D.

AFFIDAVIT

State of Kansas County of Barton

I, Cecil M. Olson, employee of the owner, do swear that the statements and matter herein contained are true to the best of my knowledge.

THE DUKE DRILLING COMPANY

BY: C. Olson

Subscribed and sworn before me this 3 day of October, 1956.

Clair E. Stinson
NOTARY PUBLIC

My commission expires: June 24, 1959.

RECEIVED
STATE CORPORATION COMMISSION
OCT 4 X 1956
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC. 33 T. 20 R. 12W
BOOK PAGE 104 LINE 7