

15-135-20866-0000

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

APR 17 1974

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Phillips Petroleum Co.

Complete Address Box 287, Great Bend, Kansas 67530

Lease Name Sutton "AB" Well No. 1

Location 1980' FEL & 660' FSL of NE/4 Sec. 15 Twp. 20 Rge. (E) (W) 23

County Ness Total Depth 4480'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Slawson Drilg.

Address Wichita, Kansas License No.

Operation Completed: Hour 9:25 P Day 14 Month 4 Year 1974

The above well was plugged as follows:

RTD 4480' 8 5/8 csg set at 500' cwe

Gunned pits, circulated heavy mud, displaced 75 sk cement plug (4460-4260) thru

drill pipe. Heavy mud to 1100' -displaced 50 sk cement plug (1100-1000) thru drill

pipe. Heavy mud to 560' -displaced 50 sk cement plug (560-460) thru drill pipe.

Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Geo L. Glasser
Well Plugging Supervisor

INVOICED

DATE 4/17/74

INV. NO. 8941-W