

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

LOCATION NE-NW-NE

Dry Hole	Abandoned Oil Well	☒	Abandoned Gas Well
----------	--------------------	-------------------------------------	--------------------

Well No. 4 Lease Faucett

Operator Abern Drilling Co. Address Box #45- Ellinwood-Kans.

Field _____ County Barton

Total Depth 3409 Feet.

Surface Pipe 8 $\frac{1}{2}$ " - 263 ft. - Circulated with cement
5 $\frac{1}{2}$ " casing at 3379 ft. - 150 sacks of cement - Plugged
back to 3170 ft. with Lane Wells Plug & Chat. - Pumped
1 sack of cement at 3170 ft. - Shot off & pulled the
5 $\frac{1}{2}$ " casing - run to 263 ft. - Set rock bridge &
10 sacks of cement at 263 ft. - run to 35 ft. bridge
& 10 sacks of cement at the surface -
Pipe Pulling, Inc. Plugging Contractors

G. H. Storch
District Conservation Agent

Date 9-5-62

PLUGGING

CONSERVATION DIVISION

FILE SEC-34 T-20 R-1200 Wichita, Kansas

BOOK PAGE 38 LINE 44