

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15.009.14569.0000

LEASE NAME Scheufler

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER #3

E/2.E/2 SW/4
1320 Ft. from S Section Line

2970 Ft. from E Section Line

SEC. 16 TWP. 20 RGE. 11 (E) or (W)

COUNTY Barton

LEASE OPERATOR Tomlinson Oil Co., Inc.

ADDRESS P.O. Box 1588

PHONE#(316) 792-2361 OPERATORS LICENSE NO. 5025

Date Well Completed 5-19-50

Character of Well SWD

Plugging Commenced 7-21-87

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 7-24-87

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? District #6 Hays, Kansas

Is ACO-1 filed? If not, is well log attached? Yes

Producing Formation Depth to Top Bottom T.D. 3920'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	288	none
				4 1/2"	3608	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Pulled 303' 2 1/2" 10rd regular cement line tbq, fished tbq, got 6" piece, 2nd fish a 3' piece, 3rd fish a 30" piece, got hold of 4th fish, drilled thru top of fish with 1 3/4" carrot mill, drilled to 712' with 1" IJ tbq. Pulled out of hole, run back in open ended, pumped 25 sx plug of common cement, pulled 1" out of hole. Rig up wireline & tried to shoot tbq off 3 times.
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor License No.

Address

STATE OF COUNTY OF , ss.


Joe Casper (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

JUL 28 1987 (Signature) Joe Casper

(Address) P.O. Box 1588 Great Bend, Ks. 67530

CONSERVATION DIVISION

SUBSCRIBED AND SWORN to before me this 27th day of July, 19 87



Shelly Shelton
Notary Public

Expires: July 8, 1991

Didn't shoot in two, tried to release overshot & could not. Rig up wireline, tried to back off twice with string shot, shot 3rd string shot with drill collar load, tried to pull overshot and started rolling casing in on top of overshot. RIH 2 jts set in tight spot, backed off 2 jts. POH and lay down. B J Hughes started cement circ. out 8 5/8" and 4 1/2", hooked to 4 1/2" and started squeeze. Pumped 312 sx econolite, shut down at 500# and held. Left overshot and 9 jts. 2" tubing in hole. Unable to pull overshot out of hole.

WELL LOG

The Henderson Oil Company et al - owners - Schouffler #3
E/2 E/2 SW/4
Sec. 16 - Twp 20 - Rg 11W
Barton County, Kansas.
SW DW

Elevation 1768 Rotary Bushing

Tops at rotary bushing

Figures indicate bottom of formation

Topeka 2648
Heebner 2914
Brown Lime 3041
Lansing 3061
Congl. 3309
Arbuckle 3503
Basal Sand 3858
Granite Wash 3883
Granite 3918

0 - 115 Sand and gravel
205 Shale and shells
288 Red bed and shale
510 Red bed
540 Anhydrite
1385 Shale and shells
1860 Shale and shells
2400 Shale and lime
2760 Lime and shale
2955 Lime
3070 Shale and lime
3330 Lime
3505 Congl.
3858 Lime
3883 Sand
3918 Granite Wash
3920 Granite
3920 T.D.

Casing Record:

8 5/8" set at 288'
4 1/2" set at 3608'

Rotary commenced April 21, 1950
Rotary completed May 5, 1950

Cable Tools commenced May 8, 1950
Cable Tools completed May 19, 1950

CABLE TOOL WORK:

Clean out
Perforate 24 holes 3082-84
Squeeze perforation w/25 sacks
Cleanout to bottom
Test - 450 B P H Thru 2"

STATE OF KANSAS }
COUNTY OF SEDGWICK } SS

I, J. A. Henderson, Secretary of The Henderson Oil Company, part owner of the above described well, being first duly sworn on oath, declare: That, I have knowledge of the facts, statements, and matters herein contained pertaining to the log of the above described well, and that the same are true and correct.

STATE CORPORATION COMMISSION

MAY 27 1950

Sworn and subscribed to before me this 20th day of May, 1950.

CONSERVATION DIVISION
Wichita, Kansas

J. A. Henderson

Ira Swanson

WELL LOG

The Henderson Oil Company et al - owners -

Scheufler #3

E/2 E/2 SW/4

Sec. 16 - Twp 20 - Rg 11W

Barton County, Kansas.

SW DW

Elevation 1768 Rotary Bushing

Tops at rotary bushing

Topoka	2648
Heebner	2914
Brown Lime	3041
Lansing	3061
Congl.	3309
Arbuckle	3503
Basal Sand	3658
Granite Wash	3883
Granite	3918

Casing Record:

8 5/8" set at 288'
4 1/2" set at 3603'

Rotary commenced April 21, 1950
Rotary completed May 5, 1950

Cable Tools commenced May 8, 1950
Cable Tools completed May 19, 1950

Figures indicate bottom of formation

0 -	115 Sand and gravel
	205 Shale and shells
	288 Red bed and shale
	510 Red bed
	540 Anhydrite
	1385 Shale and shells
	1860 Shale and shells
	2400 Shale and lime
	2760 Lime and shale
	2955 Lime
	3070 Shale and lime
	3330 Lime
	3505 Congl.
	3858 Lime
	3883 Sand
	3918 Granite Wash
	3920 Granite
	3920 T.D.

CABLE TOOL WORK:

Clean out
Perforate 24 holes 3082-84.
Squeeze perforation w/25 sacks
Cleanout to bottom
Test - 450 B P H Thru 2"

STATE OF KANSAS }
COUNTY OF SEDGWICK } SS

I, J. A. Henderson, Secretary of The Henderson Oil Company, part owner of the above described well, being first duly sworn on oath, declare: That, I have knowledge of the facts, statements, and matters herein contained pertaining to the log of the above described well, and that the same are true and correct.

JUL 28 1987

Sworn and subscribed to before me this 20th day of May, 1950.

J. A. Henderson

John S. ...

My commission expires April 28th, 1954.