


15.009.04851.0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Commission
245 North Water
Wichita, KS 67202

FORM CP-4

WELL PLUGGING RECORD



Locate well correctly on above
Section Plot

Barton County, Sec. 16 Twp. 20 Rge. 11 (E) (W)
Location as "NE/CNW/SW" or footage from lines C W/2 E/2
Lease Owner Kelso Casing Pulling
Lease Name Scheufler #4 Well No. _____
Office Address Box 176, Chase, Kansas 67524
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 3/17/76 _____ 19____
Plugging completed 3/19/76 _____ 19____
Reason for abandonment of well or producing formation depleted.
If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Rankin
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3307 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS				CASING RECORD		
FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	280	none
				4 1/2"	3305	1543

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Sanded to 3280' and ran 4 sacks cement. Shot pipe at 2000', pulled 70 joints. Bailed hole to 300' and set rock bridge 300' to 280' with 4 yards ready mix.

PLUGGING COMPLETE.

CONSERVATION DIVISION
WICHITA, KANSAS

Name of Plugging Contractor KELSO CASING PULLING
Address CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE
R. DARRELL KELSO (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
CHASE, KANSAS
(Address)

Subscribed and sworn to before me this 22nd day of March, 1976

My commission expires _____
NOTARY PUBLIC
MARGARET MELCHER
Rice County, Ks.
My Comm. Exp. Feb. 15, 1979

Margaret Melcher
Notary Public.

WELL LOG

The Henderson Oil Company et al - owners - Scheufler #4
C W/2 E/2 SE/4
Section 16-20-11W
Barton County, Kansas

Elevation 1773 R. B.

Tops at Rotary Bushing

Figures indicate bottom of formation

Topeka 2653
Heebner 2918
Brown Lime 3045
Lansing 3064
Arbuckle 3304

0 - 105 Sand and gravel
160 Shale
190 Sand
508 Red bed and shells
540 Anhydrite
1060 Shale and shells
1220 Shale and salt
1425 Shale and shells
1490 Shale and lime
1630 Lime
1745 Lime and shale
1925 Lime
2820 Lime and shale
2925 Lime
3045 Lime and shale
3307 Lime
3307 T.D. R.B.

Pipe Record:

8 5/8" set at 280'
4 1/2" set at 3305'

RECEIVED
MAR 01 1970
CONSERVATION DIVISION
Wichita, Kansas

CABLE TOOL WORK:

Clean out
3307- 3317 Lime

STATE OF KANSAS)
COUNTY OF SEDGWICK) SS

I, J. A. Henderson, Secretary of The Henderson Oil Company, part owner of the above described well, being first duly sworn on oath, declare: That, I have knowledge of the facts, statements, and matters herein contained pertaining to the log of the above described well, and that the same are true and correct.

Sworn and subscribed to before me this 15th day of July 1950

Dora Swanson
NOTARY PUBLIC

My commission expires April 28th, 1954.